

**RECEIVED**  
JUL 2 1992

SITE ASSESSMENT SECTION

General Hydraulics  
L2010450022/Winnebago Co.  
ILD 984767806

# **CERCLA**

## **Screening Site Inspection Report**

Volume 1 of 2



**Illinois Environmental  
Protection Agency**  
P.O. Box 19276  
Springfield, IL 62794-9276

EPA Region 5 Records Ctr.



326032

## TABLE OF CONTENTS

<u>SECTION</u>	<u>PAGE</u>
1 INTRODUCTION.....	1-1
2 SITE BACKGROUND.....	2-1
2.1 INTRODUCTION.....	2-1
2.2 SITE DESCRIPTION.....	2-1
2.3 SITE HISTORY.....	2-1
2.4 APPLICATION OF OTHER STATUTES.....	2-11
3 SSI ACTIVITIES AND ANALYTICAL RESULTS.....	3-1
3.1 INTRODUCTION.....	3-1
3.2 SITE REPRESENTATIVE INTERVIEW.....	3-1
3.3 RECONNAISSANCE INSPECTION.....	3-4
3.4 SAMPLING PROCEDURES.....	3-5
3.5 SOIL SAMPLING PROCEDURES.....	3-7
3.6 GROUNDWATER SAMPLING PROCEDURES.....	3-8
3.7 DECONTAMINATION PROCEDURES.....	3-9
3.8 ANALYTICAL RESULTS FROM SSI SAMPLES.....	3-10
3.9 KEY SAMPLE RESULTS.....	3-18
4 IDENTIFICATION OF SOURCES.....	4-1
4.1 CONTAMINATED SOIL PILE.....	4-1
4.2 CONTAMINATION UNDER THE BUILDING.....	4-2
4.3 ABANDONED DRUM AREA.....	4-2
5 DISCUSSION OF MIGRATION PATHWAYS.....	5-1
5.1 INTRODUCTION.....	5-1
5.2 GROUNDWATER.....	5-1
5.3 SURFACE WATER.....	5-4
5.4 AIR.....	5-5
5.5 ON-SITE EXPOSURE.....	5-6
6 BIBLIOGRAPHY.....	6-1

<u>FIGURE</u>		<u>PAGE</u>
2-1	STATE OF ILLINOIS LOCATION MAP.....	2-2
2-2	SITE LOCATION MAP.....	2-4
2-3	WARZYN SAMPLE LOCATION MAP.....	2-10
3-1	SITE FEATURES.....	3-3
3-2	SOIL/GROUNDWATER SAMPLE LOCATION MAP.....	3-6
<u>TABLE</u>		<u>PAGE</u>
2-1	SOIL GAS SURVEY RESULTS.....	2-7
2-2	GROUNDWATER SAMPLING RESULTS SUMMARY.....	2-8
2-3	SOIL SAMPLING RESULTS SUMMARY.....	2-9
3-1	SOIL SAMPLE DESCRIPTIONS.....	3-8
3-2	GROUNDWATER SAMPLE DESCRIPTIONS.....	3-9
3-3	KEY SAMPLE RESULTS.....	3-11
5-1	PUBLIC WELLS W/IN 4 MILES.....	5-2
5-2	TOTAL POPULATION ON PRIVATE AND PUBLIC WELLS..	5-3
5-3	TARGET POPULATION CALCULATION.....	5-5
<u>APPENDIX</u>		<u>PAGE</u>
A	GROUNDWATER 4-MILE RADIUS MAP.....	A-1
B	SURFACE WATER ROUTE MAP.....	B-1
C	USEPA FORM 2070-13.....	C-1
D	TARGET COMPOUND LIST.....	D-1
E	WELL LOGS.....	E-1
F	IEPA SITE PHOTOGRAPHS.....	F-1
G	1987 RAPPS REPORT (M. Well Logs and GW Flow)..	G-1
H	1990 WARZYN REPORT.....	H-1
I	ANALYTICAL RESULTS (see Volume 2 of 2).....	I-1

## 1. INTRODUCTION

On September 24, 1991, the Illinois Environmental Protection Agency's (IEPA) Pre-Remedial Unit was tasked by the United States Environmental Protection Agency (USEPA) to conduct a CERCLA Screening Site Inspection (SSI) of General Hydraulics.

General Hydraulics was added to the Comprehensive Environmental Response Compensation and Liability Act's Information System (CERCLIS) on November 29, 1988 in response to requests for discovery by the Illinois Environmental Protection Agency (IEPA). The request was initiated after abandon, leaking drums and contaminated soils were found at the site. The site received it's initial CERCLA evaluation through a Preliminary Assessments (PA) conducted in May, 1990, by Mr. Tim Murphy of IEPA. IEPA's Pre-Remedial Unit then prepared a SSI work plan for General Hydraulics that was submitted to USEPA Region V in October, 1991. The sampling portion of the SSI was conducted on November 5 and 6, 1991 when personnel from the Agency's Pre-Remedial Unit collected sixteen samples (nine groundwater and seven soil).

The purpose of an CERCLA SSI have been stated by USEPA in a directive outline of Pre-Remedial Program strategies. The directive states:

All sites will receive a screening SI to 1) collect additional data beyond the PA to enable a more refined preliminary HRS [Hazard Ranking System] score, 2) establish priorities among sites most likely to qualify for the NPL [National Priorities List], and 3) identify the most critical data requirements for the listing SI step. A Screening Si will not have rigorous data quality object-



ives (DQOs). Based on the refined preliminary HRS score and other technical judgement factors, the site will then either be designated as NFRAP [no further remedial action planned], or carried forward as an NPL listing candidate. A listing SI will not automatically be done on these sites, however. First, they will go through a management evaluation to determine whether they can be addressed by another authority such as RCRA (Resource Conservation and Recovery Act).... Sites that are designated NFRAP or deferred to other statutes are not candidates for a listing SI.

The listing SI will address all the data requirements of the revised HRS using field screening and NPL level DQOs. It may also provide needed data in a format to support remedial investigation work plan development. Only sites that appear to score high enough for listing and that have not been deferred to another authority will receive a listing SI. (USEPA 1988)

The Region V offices of the USEPA have also requested that the IEPA identify sites during the SSI that may require removal action to remediate an immediate human health and/or environmental threat.

## 2. SITE BACKGROUND

### 2.1 INTRODUCTION

This section includes information obtained over the course of the formal CERCLA SSI investigation, as well as through previous IEPA findings and a recent investigation preformed by a contractor (Warzyn) for North American Tool Corporation (NATCo).

### 2.2 SITE DESCRIPTION

General Hydraulics is the name of a defunct business that had operated a lawn and garden equipment manufacturing facility in South Beloit, Illinois. The facility was comprised of three, one-story buildings on eight acres of land, 450 feet east of the Rock River. The facility was located in an industrial and residential area, near the center of the city (population 4,088). More specifically, the site is west of Hayes Avenue and between Charles Avenue to the north and Elmwood Avenue to the south. The legal description would include the site within the southeast quarter of Section 6, Township 46 north, Range 2 east of the Third Principle Meridian in Winnebago County. A 4-mile radius map of General Hydraulics can be viewed in Appendix A. The following page shows the site location with respect to the State of Illinois.

### 2.3 SITE HISTORY

Prior to General Hydraulics, the Chicago, Minneapolis, St. Paul and Peoria Railroad owned the site as part of their right-of-way. The Railroad allowed fill material to be

Figure 2-1



SITE LOCATION


dumped in the swampy areas of the site, thus raising the elevation by several feet in certain areas. The dumping (destroying the wetland) also helped level the site and surrounding area for future uses.

Mr. Glen Hanson began his manufacturing at General Hydraulics after he purchased eight acres from the railroad in the early 1950's. General Hydraulics built various equipment including farm sprayers, mowers and snow blowers. The three, one-story buildings at the facility served specific functions. The metal building in the northeast corner of the property, housed the fiberglass operation. Tanks and sprayers were built there. Welding and fabrication took place in the metal building west of the fiberglass operation (the northwest area of the property). The third General Hydraulics building was the masonry construction on the south end of the property. Here, Mr. Hanson had his machine shop. A site location map, Figure 2-2 on the following page, depicts the three buildings.

Much of General Hydraulics wastes were generated at the machine shop in the form of cutting oils and solvents. In April of 1981, IEPA discovered that the facility was using a Wisconsin transport company to ship wastes without manifests.

In 1984, General Hydraulics declared bankruptcy and in 1985, the bankruptcy court parceled the property for sale. One prospective buyer, Magnetic Data Carriers rescinded their purchase agreement after abandoned, leaking drums of waste and visibly contaminated soil were found at the site.





Source: IEPA, 1992 Base Map: USGS, 1976 South Beloit, Ill.-Wis.  
Scale 1:24,000

Figure 2-2  
SITE LOCATION MAP

IEPA inspected the site on May 2, 1986, after Magnetic Data Carriers had reported the waste left behind by General Hydraulics. At the site, IEPA discovered two separate dumping areas. At one area, a reddish-brown granular material was observed and the other area had a mixture of materials (drums, pails, wooden crates, tires, trash, etc). The entire site was littered with trash and debris. It was estimated that 112-120, 55 gallon drums and 25-50 five gallon pails had been left on-site.

The bankruptcy court contracted Frinks Industrial Waste (FIW) to sample and remove the waste. Composite samples were obtained from the drums and analyzed for corrosive, ignitability, total metals, and certain other hazardous characteristics. Nine drums were found to contain hazardous waste based on flash point. All of the drums were staged and disposed of by FIW. Several soil samples showed EP Toxic for lead, chromium and barium.

During the drum removal, an on-site well was sampled. The 15 foot well serves the current operation and employees at Trenwyth Midwest Industries (purchased the northwest parcel with the welding and fabrication building). The results showed that the well was contaminated with tetrachloroethene (PCE) at a concentration of 1.8 ug/l (ppb). Later sampling of Trenwyth well and another on-site well at Hanson General Products (Mr. Hanson retained control of the smallest parcel with the fiberglass operation) confirmed the groundwater contamination of PCE at 1.4 and 1.3 ug/l



respectively.

A stand pipe located near the machine shop (now NATCo) was alleged to be used for disposal of wastes. The pipe went into a buried 55 gallon fiberglass drum. FIW sampled the drum contents and soil beneath the drum and found no volatiles. The pipe and drum were subsequently sealed with concrete.

The bankruptcy court contracted M. Rapps Associates, Incorporated to do a groundwater study of the site. M. Rapps had four monitor wells installed on the property in early 1987. The wells showed a very slight gradient of groundwater movement toward the west-southwest. Two of the wells contained levels of PCE contamination at 5.8 ug/l (ppb) in G101 and 4.8 ug/l in G104.

In 1990, NATCo contracted Warzyn to conduct a soil gas survey and collect soil and groundwater samples from their facility. What follows are three tables and a map from this report that show soil and groundwater contamination at the south end of the former General Hydraulics operation.

Table 2-1

Soil Gas Survey Results  
North American Tool Corporation  
South Beloit, Illinois

Soil Gas Sampling Location	Field Screening With HNu ppm(1)	Laboratory Analytical Results	
		Compound(2)	Concentration (ug/L of soil gas)
SG01	ND	ND	-
SG02	ND	ND	-
SG03	11-15 (11-15)	1,1-Dichloroethene	119 (118)
		cis-1,2-Dichloroethene	514 (499)
		Trichloroethene	17.3 (20.9)
		Tetrachloroethene	15.0 (17.8)
SG04	ND	cis-1,2-Dichloroethene	1.04
SG05	ND	ND	-
SG06	ND	ND	-
SG07	0.5	ND	-
SG08	ND	ND	-
SG09	3.0	Trichloroethene	<1.00
		Tetrachloroethene	36.4
SG10	1.0	1,1-Dichloroethene	3.61
		cis-1,2-Dichloroethene	84.5
		Trichloroethene	18.0
		Tetrachloroethene	27.2
SG11	1.0	ND	-
SG12	0.8	ND	-
SG13	0.5	ND	-
SG14	NA	ND	-

**NOTES:**

ND = No Detects

NA = Not Analyzed

&lt;1.00 indicates concentration below method quantitation limit of 1.00 ug/L soil gas.

(1) ppm total volatile organics above background (reported as benzene equivalent)

(2) Sample chromatograms for soil gas samples SG03, SG04, SG09 and SG10 also contain unidentified compounds.

(3) Concentrations in parenthesis are from SG03 duplicate sample.

PFJ/vlr/APA/KJQ

[jlv-403-90]

15275.00-MD



Groundwater Sampling Results Summary  
North American Tool Corporation  
South Beloit, Illinois

<u>Location</u>	<u>Compound</u>	<u>Concentration</u> (ug/L)	<u>Groundwater(3)</u> <u>Quality Criteria</u> (ug/L)
MW1	Tetrachloroethene	1.18	5
MW2	1,1-Dichloroethane	16.5	-
	1,1-Dichloroethene	2.15	7
	cis-1,2-Dichloroethene	4.91	70
	Tetrachloroethene	1.10	5
	1,1,1-Trichloroethane	66.3	200
MW3	Trichloroethene	3.28	5
	Tetrachloroethene	2.23 (1.78)	5
	1,1,1-Trichloroethane	1.25 (1.14)	200
Excavation Ground- water	1,1-Dichloroethene	1180	7
	1,1,1-Trichloroethane	9150	200

NOTES:

1. Sampling performed on August 30, 1990.
2. ( ) concentrations indicate results of duplicate sample (MW3 Dup) analysis.
3. Groundwater quality criteria from Title 35, Section 620.301, Illinois Administrative Code. (same as maximum concentration levels; U.S. EPA office of Drinking Water, April 1990 for those compounds)
4. - indicates standard not available for this compound

PFJ/vlr/APA/KJQ  
[Jlv-403-89]  
15275-MD

Table 2-2

Soil Sampling Results Summary  
North American Tool Corporation  
South Beloit, Illinois

Sample Location (1)Q	Sample Depth (ft)	Compound	Concentration (ppm)
SB 03	1-1.5	Tetrachloroethene	<0.050
		1,1,1-Trichloroethane	0.422
		Trichloroethene	0.214
NE	—	1,1,1-Trichloroethane	0.129
		Trichloroethene	0.0526
		Xylenes	<0.050
NW	—	Toluene	<0.050
		1,1,1-Trichloroethane	0.135
		Trichloroethene	<0.050
SE	—	Toluene	<0.050
SW	—	Toluene	<0.050
		1,1,1-Trichloroethane (2)	0.0673
Excavated Soil		1,2-Dichlorobenzene	1.450
		1,2-Dichloroethane	<0.050
		Ethyl Benzene	0.806
		Tetrachloroethene	1.240
		1,1,1-Trichloroethane	1.570
		Xylenes (2), (3)	14.600

Table 2-3

<.050 = detected below quantitation limit of .050 mg/kg.

(1) Samples obtained from SB03, and from the NE, NW, SE and SW corners of the soil excavation (Refer to Drawing 15275-B1)



(2) Unidentified compounds also detected

(3) Sample also analyzed for total petroleum hydrocarbons (TPH). Sample contains unknown hydrocarbons. Estimated concentration of TPH is 2190 mg/kg, based on the gasoline standard.

PFJ/vlr/APA/KJQ  
[jlv-403-88]  
15275.00-MD

Figure 2-3

- LEGEND**
- ⊗ SG1 SOIL GAS SAMPLING LOCATION AND NUMBER
  - SB3 SOIL SAMPLING LOCATION AND NUMBER
  - ⊕ MW1 MONITORING WELL LOCATION, NUMBER AND WATER TABLE ELEVATION (731.98)
- NOTES**
1. BASE MAP DEVELOPED FROM PLAT OF SURVEY PROVIDED BY R.H. BATTERMAN AND CO., INC. DATED NOVEMBER 22, 1988. REVISED OCTOBER 1, 1990.
  2. SOIL GAS SURVEY AND SOIL SAMPLING PERFORMED BY WARZYN ENGINEERING INC. ON AUGUST 28-30, 1990.
  3. SOIL SAMPLES FROM THE FOUR CORNERS OF THE 6 FT. DEEP EXCAVATION (APPROXIMATELY 18 FT. X 43 FT.) OBTAINED BY WARZYN ENGINEERING INC. ON SEPTEMBER 10, 1990.
  4. WITHIN THE EXCAVATION, A 6 FT. X 6 FT. AREA AROUND SG3 WAS EXCAVATED TO A DEPTH OF 7 FT., AND THE GROUNDWATER WAS SAMPLED BY WARZYN ENGINEERING INC. ON SEPTEMBER 10, 1990.
  5. WATER LEVEL MEASUREMENTS PERFORMED ON OCTOBER 28, 1990 BY WARZYN ENGINEERING INC.



#### 2.4 APPLICATION OF OTHER STATUTES

Two of the three facilities now in operation at the General Hydraulics site are regulated by other environmental statutes. The two facilities are small quantity generators as regulated by the Resource Conservation and Recovery Act (RCRA). Both Accra Plastics (ILD 102372315) and NATCo (ILD 151870409) store RCRA wastes. Accra Plastics also has an air pollution permit (ID # 201045ABB application # 88070083) as regulated under the Clean Air Act (CAA).

General Hydraulics was a non-notifier that declared bankruptcy in 1985 and subsequently was not regulated by RCRA.

### 3. SSI ACTIVITIES AND ANALYTICAL RESULTS

#### 3.1 INTRODUCTION

This section outlines procedures utilized and observations made during the CERCLA SSI, conducted at General Hydraulics. Specific portions of this section contain information pertaining to the site representative interviews, reconnaissance inspection, field sampling procedures and key analytical findings. The SSI for General Hydraulics was conducted in accordance with the work plan, which was developed and submitted to USEPA Region V, prior to the initiation of field activities.

USEPA's Potential Hazardous Waste Site Inspection Report (Form 2070-13) for each of the Sites is located in Appendix C of this report.

#### 3.2 SITE REPRESENTATIVE INTERVIEWS

Site representative interviews were conducted on October 22, 1991, between IEPA's Tim Murphy and the representatives for two of the three facilities now in operation on the parceled General Hydraulics site. The purpose of the meetings were to gain access agreements and gather additional information on the site.

Because company officials were at lunch at the time of arrival, this author proceeded in obtaining sample agreements with the private well owners on Hayes Avenue and arranging the off-site, background soil sample location. Two cooperative home-owners gave their consent along with the idea that they would inform the others on the block that IEPA


was planning to sample their wells in the coming weeks. At 12:40 pm, Sister David of St. Peters School was interviewed and granted permission to sample the school yard soil for background. Sister David said that 95 students are enrolled at the school, ranging from pre-school (3 years old) to eighth grade. She also said that the school was supplied with city water.

Cy Hotek and Dave Saunders of Trenwyth Midwest Industries (208 Charles Avenue) were interviewed at 1:12 pm. In 1986, the bankruptcy court sold Trenwyth the second largest of three parcels of land comprising the original General Hydraulics site. Trenwyth converted the General Hydraulics welding and fabrication shop for use in their acrylic glaze operation. Various types of building block and acrylic glaze are delivered to the operation. Trenwyth Midwest creates a marketable product after grinding the block face and glazing over it. The process involves 81 company employees. Drinking water is charcoal filtered from the 15 feet contaminated well at the facility. Mr. Saunders stated that their operation generates no hazardous waste.

Representing NATCo was president, Roger Taylor, Vice President, Curt Lansbury and their attorney, Burk Giessler. The meeting started with an explanation of portions of the CERCLA Pre-remedial process. NATCo manufactures tap and die tools. The company recently purchased equipment which will enable them to recycle some of their cutting fluids. As mentioned on page 2-11, NATCo maintains a less than 90 day

SCALE 1" = 50'

Figure 3-1  
Site Features



NOTE: E 1" DESIGNATES FOUND 1" IRON PIN  
F 3/8" DESIGNATES FOUND 3/8" IRON PIN  
F 1/2" DESIGNATES FOUND 1/2" IRON PIN  
F 3/4" DESIGNATES FOUND 3/4" IRON PIN  
F 1" DESIGNATES FOUND 1" IRON PIN

storage pad for RCRA generated wastes.

The meeting proceeded with a tour of NATCo's new addition. The addition is built over the area where the stand pipe/buried drum was alleged to have been used for discarding General Hydraulics machine shop waste. At this time, the previously mentioned (page 2-6) 1990, Warzyn report was explained. Mr. Taylor informed this author that samples had been taken and contaminated soil removed prior to the building of the addition. Later (4:10 pm), Mr. Giessler presented a copy of Warzyn report to this author at his Rockford office.

This author stopped in at Accra Plastics two times throughout the day, but nobody was available for the interview. Instead, a short interview took place later, during the CERCLA SSI on November 5, 1991. Mr. John Wilborg and this author discussed the Pre-remedial process along with his concern over liability. Mr. Wilborg informed this author that Accra Plastics is a combined company with Hanson General Products, the company that was formed after the General Hydraulics bankruptcy. The smell of styrene from the operation was very strong, even throughout the Hayes Avenue neighborhood. Mr. Wilborg stated that the company is permitted for paint booths #1 and #2 (air permit issued September, 1988). The company supplies bottled water for its 10-15 employees.

### 3.3 RECONNAISSANCE INSPECTION

The site reconnaissance inspection for General



Hydraulics was conducted after the interviews on October 22, 1991 by this author. The site is bound on the north by Charles Avenue, across which contained undeveloped property owned by Cliff Tricke; on the west by the C. M. St. Paul and P. Railroad; on the south by Elmwood Avenue and undeveloped property; and on the east by the Hayes Addition residents (8 residential dwelling units along Hayes Avenue). Figure 3-1 on page 3-3 of this report, shows the prominent site features.

After seeing the new NATCo's new addition, this author and Mr. Lansbury checked the integrity and took water levels of the three monitor wells. The forth well was destroyed when a portion of Trenwyth Midwest Industries was paved over. The well protective covers were locked and two of the well's stainless steel casings were capped with cut-off, aluminum pop cans. Two of the monitor wells showed HNu photoionization detector (PID) levels slightly above background (1.5 units) while the third well in the southwest corner of the site, had a level 6.5 units above background. Later, this author used the HNu to screen for impending sample locations. Other than the contaminated soil pile, no distinct areas of contamination were observed. This author left the site at 3:24 pm.

During the reconnaissance visit, it was determined that Modified Level D inspection attire could be worn during the sampling activities. Level C (respirator) attire would also be brought along for use if air monitoring equipment detected



significant concentrations over background or if other threatening conditions ensue.

#### 3.4 SAMPLING PROCEDURES

Samples were collected by IEPA personnel to confirm the findings in the Warzyn report (attribution of groundwater contamination to site) and determine if the adjacent private wells are being effected by the site. In each of the soil samples and two of the groundwater samples, the USEPA Target Compound List (TCL) compounds were analyzed for. The seven remaining groundwater samples were analyzed for VOC's only (the contaminants of concern). The current list of compounds on the TCL is provided in Appendix D.

On November 5 and 6, 1991, IEPA collected the nine groundwater and seven soil samples. Figure 3-2 on page 3-6 of the report depicts the locations of the sixteen sample points.

#### 3.5 SOIL SAMPLING PROCEDURES

Of the seven soil samples, six were collected on-site, within areas of suspected contamination. Only one off-site sample was collected for a background comparison. The background sample was collected at St. Peters School. Table 3-1, on the following page, describes each of the seven soil samples, listing their depth, physical appearance and location.

Table 3-1

**Soil Sample Descriptions**

<u>Sample</u>	<u>Depth</u>	<u>Appearance</u>	<u>Location</u>
X101	6"-1.5'	drk silty clay	40.5' W of new dock @ NATCo in clay center of ditch
X102	1'3"- 2'6"	drk silty clay to s&g	40' N of the NE corner of truck load- ing dock @ NATCo & 45' SW of the SW corner of Accra Plastics bldg under asphalt
X103	11"-2'	blk silty clay	60' NW of NATCo dock behind Trenwyth under asphalt
X104	1'6"- 2'4"	blk silty clay	37' N & 35' W of NATCo behind Trenwyth under asphalt
X105	1'-1.5'	s&g	90' W of the asphalt's end @ Trenwyth on the S side of ditch
X106	1'-3' angled	drk sandy silt	47' from the E end of contaminated soil pile at NATCo
X107 back- ground	6"-1.5'	drk sandy silt	22' S of edge of Elmwood Ave & 39' E of sidewalk on W side of St. Peters School between 2 maple trees

drk-dark, blk-black, s&g-sand and gravel, '-feet, "-inches, @-at, E-east, N-north, W-west, S-south, Ave-Avenue

**3.6 GROUNDWATER SAMPLING PROCEDURES**

The private wells on Hayes Avenue were sampled to determine if site contaminants were migrating throughout this neighborhood's drinking water supply. Each home owner in the neighborhood stated either that their well was shallow, or that it was less than 20 feet deep. They also said that they did not treat the water. All nine wells were purged a minimum of 20 minutes. At the beginning, in the middle and at the end of each purge time, the groundwater temperature, specific conductivity and pH were monitored. Eight of the

samples were collected from inside faucets (airators removed) and one was taken from an outside spigot. The samples collected from at 508 and 528 Hayes Avenue (G201 and G204 respectively) were analyzed for the TCL. The remaining wells on either side of the avenue, were sampled for VOC's only. Table 3-2 highlights the groundwater sample locations.

Table 3-2

**Groundwater Sample Descriptions**

<u>Sample</u>	<u>Owner</u>	<u>Well Depth</u>	<u>Block Location</u>	<u>Address</u>
G201	W.Pearson	shallow*	W side, N	508 Hayes Ave
G202	K.Schmidt	shallow*	W side, N central	522 Hayes Ave
G203	unk. 5 families	unk.	W side, central	524 Hayes Ave
G204	Neives	shallow*	W side, central	526 Hayes Ave
G205	S.Klink- hammer	< 20'	W side, S central	528 Hayes Ave
G206	A.Perry	shallow*	W side, S	530 Hayes Ave
G207	J.Baden	< 20'	E side, S central across from G205	527 Hayes Ave
G208	Willie	< 20'	E side, central	521 Hayes Ave
G209	M.McMahon	shallow*	E side, N	505 Hayes Ave

\*-owner states depth unknown but well is shallow, <-less than, unk.-unknown, E-east, N-north, W-west, S-south, Ave-avenue, '-feet

**3.7 DECONTAMINATION PROCEDURES**

Standard IEPA decontamination procedures were followed prior to the collection of all samples. All sampling equipment had previously been decontaminated at the IEPA warehouse prior to its transport to the site.

Decontamination procedures include the cleaning of all

equipment with trisodium phosphate solution, rinsing with hot tap water, acetone, hot tap water again, and finally rinsing with distilled water. All sampling equipment was dried and wrapped with aluminum foil prior to conducting any field sampling activities.

### 3.8 ANALYTICAL RESULTS FROM IEPA COLLECTED SAMPLES

Chemical analysis of groundwater samples collected from the private wells revealed the presence of the volatile contaminant tetrachloroethene (PCE) at the two homes on the north end of the block. Analysis of contaminated soil pile revealed the presence of volatiles, including PCE and 1,1,1-trichloroethane (1,1,1-TCA), polynuclear aromatic hydrocarbons (PNA's), pesticides, common laboratory artifacts, and common soil/sediment constituents. Appendix I in Volume 2 lists the analytical results from the CERCLA SSI.

### 3.9 KEY SAMPLE RESULTS

Table 3-4 summarizes the key analytical data generated during the CERCLA SSI.

Table 3-3

#### **Key Analytical Data**

<u>Sample</u>	<u>Location</u>	<u>Compound Detected</u>	<u>Concentration</u>
X107	Background from St. Peters school yard	- -	Below CRQL
X106	Contaminated Soil Pile	1,1,1-trichloroethane tetrachloroethene PNA's	3 ug/kg J 8 ug/kg 27.9 mg/kg + 7.1 mg/kg J
X103	Soil between Trenwyth and NATCo	1,2-dichloroethene toluene xylene (total)	3 ug/kg J 3 ug/kg J 5 ug/kg J
G201	508 Hayes Ave well on W side, N end	tetrachloroethene	7 ug/l
G209	505 Hayes Ave well on E side, N end	tetrachloroethene	7 ug/l

J-estimated value

The following table summarizes the entire sample data data.

# Sample Summary from IEPA Collected Samples

General Hydraulics ILD 984767806		X101 11/05/91	X102 11/05/91	X103 11/05/91	X104 11/05/91	X105 11/05/91	X106 11/05/91	X107 11/05/91
SAMPLING POINT PARAMETER								
VOLATILES (ppb)								
Methylene Chloride		8 J	15 J	35 J	25 J	5 J	23 J	4 J
Acetone		--	28 J	220 J	49 J	16 J	7 J	--
1,2-Dichloroethene(total)		--	--	3 J	--	--	--	--
2-Butanone (MEK)		13 R	8 R	68 R	10 R	11 R	12 R	13 R
1,1,1-Trichloroethane		--	--	--	--	--	3 J	--
Tetrachloroethene		--	--	--	--	--	8	--
Toluene		--	--	3 J	--	--	--	--
Xylene(total)		--	--	5 J	--	--	--	--
TIC's		--	(2)	(1)	(1)	--	(1)	--
SEMIVOLATILES (ppb)								
Acenaphthene		--	--	--	--	--	330 J	--
Dibenzofuran		--	--	--	--	--	170 J	--
Fluorene		--	--	--	--	--	370 J	--
Phenanthrene		--	--	--	--	--	3900	--
Anthracene		--	--	--	--	--	1000	--
Fluoranthene		--	--	--	--	--	6600	--
Pyrene		--	--	--	--	--	6300 J	--
Chrysene		--	--	--	--	--	3800	--
Benzo(b)fluoranthene		--	--	--	--	--	2900	--
Benzo(k)fluoranthene		--	--	--	--	--	2700	--
Benzo(a)pyrene		--	--	--	--	--	3100	--
Indeno(1,2,3-cd)pyrene		--	--	--	--	--	1900	--
Benzo(g,h,i)perylene		--	--	--	--	--	2000	--
TIC's		(7)	(6)	(5)	(9)	(5)	(19)	(7)
PESTICIDES/PCB'S (ppb)								
4,4'-DDD		--	--	--	--	--	360	--
4,4'-DDT		--	--	--	--	--	480	59
Aroclor-1254		--	--	--	--	--	35 J	--



General Hydraulics  
ILD 984767806

SAMPLING POINT	X101	X102	X103	X104	X105	X106	X107
PARAMETER	11/05/91	11/05/91	11/05/91	11/05/91	11/05/91	11/05/91	11/05/91
INORGANICS (water-ppb, soil/sed-ppm)							
Aluminum	13100	8580	13500	17500	2690	9000	9960
Antimony	15 R	13 R	14 R	14 R	13 R	13 R	13 R
Arsenic	3.8	2.6	5.0	2.4	2.6	3.1	4.0
Barium	138	69	145	182	39 B	100	143
Beryllium	0.8 B	0.5 B	0.8 B	1.0 B	0.3	0.6 B	--
Cadmium	--	--	--	--	0.4	--	--
Calcium	33900	13300	11600	10000	53300	12000	4100
Chromium	39	16	23	28	12	27	18
Cobalt	8.1 B	4.9 B	6.5 B	11 B	2.1	4.4 B	5.7
Copper	46 J	6.9 J	13 J	16 J	6.5 J	78 J	12 J
Iron	20400	12600	19100	22700	11000	13400	12300
Lead	30.3	6.6	14.2	13.7	5.3	42	27.8
Magnesium	18500	7900	6200	5200	32400	4200	2300
Manganese	810	416	730	1000	397	325	810
Mercury	0.05B	--	--	--	--	--	--
Nickel	35	9.1 B	17	20	12	33	13
Potassium	1560	655 B	1030 B	1100 B	420 B	580 B	1400
Selenium	0.3 J	0.3 J	0.3 J	0.3 J	0.3 J	0.3 BJ	0.3 J
Silver	--	--	--	--	--	--	--
Sodium	--	--	--	--	--	--	--
Thallium	0.5 BJ	0.1 J	0.3 BJ	0.2 BJ	0.1 J	0.4 BJ	0.7 BJ
Vanadium	26	18	28	34	22	21	24
Zinc	170	39	66	86	19	115	64
Cyanide	--	--	--	--	--	--	--
Sulfate	--	--	--	--	--	--	--
Sulfide	--	--	--	--	--	--	--

General Hydraulics  
ILD 984767806

SAMPLING POINT PARAMETER	G201 11/06/91	G202 11/06/91	G203 11/06/91	G204 11/06/91	G205 11/06/91	G206 11/06/91	G207 11/06/91	G208 11/06/91	G209 11/06/91
VOLATILES (ppb)									
Methylene Chloride	--	--	--	--	--	--	--	--	--
Acetone	17 J	--	--	--	--	--	--	--	--
1,2-Dichloroethene(total)	--	--	--	--	--	--	--	--	--
2-Butanone (MEK)	10 R	10 R	10 R	10 R	10 R	10 R	10 R	10 R	10 R
1,1,1-Trichloroethane	--	--	--	--	--	--	--	--	--
Tetrachloroethene	7	--	--	--	--	--	--	--	7
Toluene	--	--	--	--	--	--	--	--	--
Xylene(total)	--	--	--	--	--	--	--	--	--
TIC's									
SEMIVOLATILES (ppb)									
Acenaphthene	--	--	--	--	--	--	--	--	--
Dibenzofuran	--	--	--	--	--	--	--	--	--
Fluorene	--	--	--	--	--	--	--	--	--
Phenanthrene	--	--	--	--	--	--	--	--	--
Anthracene	--	--	--	--	--	--	--	--	--
Fluoranthene	--	--	--	--	--	--	--	--	--
Pyrene	--	--	--	--	--	--	--	--	--
Chrysene	--	--	--	--	--	--	--	--	--
Benzo(b)fluoranthene	--	--	--	--	--	--	--	--	--
Benzo(k)fluoranthene	--	--	--	--	--	--	--	--	--
Benzo(a)pyrene	--	--	--	--	--	--	--	--	--
Indeno(1,2,3-cd)pyrene	--	--	--	--	--	--	--	--	--
Benzo(g,h,i)perylene	--	--	--	--	--	--	--	--	--
TIC's									
PESTICIDES/PCB'S (ppb)									
4,4'-DDD	--	--	--	--	--	--	--	--	--
4,4'-DDT	--	--	--	--	--	--	--	--	--
Aroclor-1254	--	--	--	--	--	--	--	--	--

General Hydraulics  
ILD 984767806

SAMPLING POINT PARAMETER	G201 11/06/91	G202 11/06/91	G203 11/06/91	G204 11/06/91	G205 11/06/91	G206 11/06/91	G207 11/06/91	G208 11/06/91	G209 11/06/91
INORGANICS (water-ppb, soil/sed-ppm)									
Aluminum	--	--	--	--	--	--	--	--	--
Antimony	--	--	--	--	--	--	--	--	--
Arsenic	0.6 J	--	--	--	1.0 B	--	--	--	--
Barium	69.6 B	--	--	--	64.4 B	--	--	--	--
Beryllium	--	--	--	--	--	--	--	--	--
Cadmium	--	--	--	--	--	--	--	--	--
Calcium	91900	--	--	--	88300	--	--	--	--
Chromium	--	--	--	--	9.6 B	--	--	--	--
Cobalt	--	--	--	--	--	--	--	--	--
Copper	--	--	--	--	9.4	--	--	--	--
Iron	--	--	--	--	--	--	--	--	--
Lead	1.7 BJ	--	--	--	0.7 J	--	--	--	--
Magnesium	36900	--	--	--	37100	--	--	--	--
Manganese	--	--	--	--	--	--	--	--	--
Mercury	0.17	--	--	--	0.12	--	--	--	--
Nickel	11 J	--	--	--	11 J	--	--	--	--
Potassium	3840 B	--	--	--	4640 B	--	--	--	--
Selenium	1.6 BJ	--	--	--	1.6 BJ	--	--	--	--
Silver	--	--	--	--	--	--	--	--	--
Sodium	29600	--	--	--	27000	--	--	--	--
Thallium	--	--	--	--	--	--	--	--	--
Vanadium	--	--	--	--	--	--	--	--	--
Zinc	28.5	--	--	--	45.3	--	--	--	--
Cyanide	--	--	--	--	--	--	--	--	--
Sulfate	45000	--	--	--	43000	--	--	--	--
Sulfide	--	--	--	--	--	--	--	--	--

FIELD TESTS

Temperature (degrees F)	59.5	57.3	53.6	60.2	55.3	57	53.4	57	52
Sp. Conductivity (Umhos)	1330	1180	1080	1280	1220	1180	1180	1240	1300
Ph	7.71	7.75	7.78	7.66	7.55	7.66	8.21	7.69	7.9

## U.S.E.P.A. DEFINED DATA QUALIFIERS

<u>QUALIFIER</u>	<u>DEFINITION ORGANICS</u>	<u>DEFINITION INORGANICS</u>
• U	Compound was tested for but not detected. The sample quantitation limit must be corrected for dilution and for percent moisture. For soil samples subjected to GPC clean-up procedures, the CRQL is also multiplied by two, to account for the fact that only half of the extract is recovered.	Analyte was analyzed for but not detected.
• J	Estimated value. Used when estimating a concentration for tentatively identified compounds (TICs) where a 1:1 response is assumed or when the mass spectral data indicate the presence of a compound that meets the identification criteria and the result is less than the sample quantitation limit but greater than zero. Used in data validation when the quality control data indicate that a value may not be accurate.	Estimated value. Used in data validation when the quality control data indicate that a value may not be accurate.
• C	This flag applies to pesticide results where the identification is confirmed by GC/MS.	Method qualifier indicates analysis by the Manual Spectrophotometric method.
• B	Analyte was found in the associated blank as well as in the sample. It indicates possible/probable blank contamination and warns the data user to take appropriate action	The reported value is less than the CRDL but greater than the instrument detection limit (IDL).
• D	Identifies all compounds identified in an analysis at a secondary dilution factor. If a sample or extract is re-analyzed at a higher dilution factor as in the "E" flag above, the "DL" suffix is appended to the sample number on the Form I for the diluted sample, and <u>all</u> concentration values are flagged with the "D" flag.	not used

QUALIFIER      DEFINITION ORGANICS

- E      Identifies compounds whose concentrations exceed the calibration range for that specific analysis. All extracts containing compounds exceeding the calibration range must be diluted and analyzed again. If the dilution of the extract causes any compounds identified in the first analysis to be below the calibration range in the second analysis, then the results of both analyses must be reported on separate Forms I. The Form I for the diluted sample must have the "DL" suffix appended to the sample number.
  
- A      This flag indicates that a TIC is a suspected aldol concentration product formed by the reaction of the solvents used to process the sample in the laboratory.
  
- M      not used
  
- N      not used
  
- S      not used
  
- W      not used
  
- \*      not used
  
- +      not used

DEFINITION INORGANICS

- The reported value is estimated because of the presence of interference
- 
- Method qualifier indicates analysis by Flame Atomic Absorption (AA).
- 
- Duplicate injection (a QC parameter) not met.
- 
- Spiked sample (a QC parameter) recovery not within control limits.
- 
- The reported value was determined by the Method of Standard Additions (MSA).
- 
- Post digestion spike for Furnace AA analysis (a QC parameter) is out of control limits of 85% to 115% recovery, while sample absorbance is less than 50% of spike absorbance.
- 
- Duplicate analysis (a QC parameter) not within control limits.
- 
- Correlation coefficient for MSA (a QC parameter) is less than 0.995.

QUALIFIER      DEFINITION ORGANICS

- P            not used
- CV           not used
- AV           not used
- AS           not used
- T            not used
- NR           The analyte was not required to be analyzed.
- R            Rejected data. The QC parameters indicate that the data is not usable for any purpose.

DEFINITION INORGANICS

- Method qualifier indicates analysis by ICP (Inductively Coupled Plasma) Spectroscopy.
- Method qualifier indicates analysis by Cold Vapor AA.
- Method qualifier indicates analysis by Automated Cold Vapor AA
- Method qualifier indicates analysis by Semi-Automated Cold Spectrophotometry.
- Method qualifier indicates Titrimetric analysis.
- The analyte was not required to be analyzed.
- Rejected data. The QC parameters indicate that the data is not usable for any purpose.

#### 4. IDENTIFICATION OF SOURCES

This section discusses the sources of contamination identified at the General Hydraulics site.

Information concerning the size, volume and waste composition of each source has been derived throughout the initial site assessment and the screening site inspection sampling action. It should be pointed out however, that the total number and nature of each of the sources identified below may be subject to change, as the site progresses through the CERCLA site investigation program and receives further investigation.

##### 4.1 CONTAMINATED SOIL PILE

Contaminated soil was excavated from the west side of the existing NATCo building (General Hydraulics machine shop) on September 10, 1990 by Selvog Excavation Inc., with oversight and monitoring by Warzyn. The excavation was centered around soil gas location SG03 (see map on page 2-10). The dimensions of the excavation were approximately 43 feet by 18 feet by 5 feet deep (3870 cubic feet). The pile was created when backhoe buckets were screened with a HNu PID (11.7 eV). Those buckets with readings above background, were stockpiled on plastic, east of the building. A composite sample from the pile found aromatics and chlorinated solvents, which have been tabled on page 2-9.

During the CERCLA SSI the pile was found to be 190 feet west of the new addition with dimensions measuring 95 feet by 16 feet by 5 feet high triangulated (length times one-half

base times height = 3800 cubic feet). The pile is on top of plastic but is not covered. The analysis of the CERCLA SSI sample collected from the center of the pile shows PNA's along with the chlorinated solvents 1,1,1-trichloroethane and tetrachloroethene

#### 4.2 CONTAMINATION SOIL UNDER NEW ADDITION

HNu reading were also used to determine the lateral extent of the excavation. As it reads in the report, the soils exhibited reading of 40-50 ppm near the soil gas location SG03, with slight or no readings above background at the excavation boundaries. On the floor of the excavation at the five feet depth, HNu reading up to 100-160 ppm were observed. Warzyn's samples from the four corners of the excavation, contained 1,1,1-trichloroethane in three of the four samples. A groundwater sample collected from the water infiltrating the pit contained higher levels of contaminants than the nearby monitor wells.

#### 4.3 ABANDONED DRUM AREA

The place where FIW removed the 112-120 abandoned drums appears to have been somewhere between or slightly west of NATCo and Trenwyth Industries in an area that has been covered with asphalt. Little is known as to the exact location or size of this possible source of contamination. During the CERCLA SSI, samples X103 and X104 were collected with this source in mind. Trace amounts of 1,2-dichloroethene, xylene and toluene were estimated in X103.



## 5. MIGRATION PATHWAYS

### 5.1 INTRODUCTION

This section includes information that may be useful in determining General Hydraulics impact on the four exposure pathways identified in CERCLA's hazard ranking system (HRS). The three migration pathways - groundwater, surface water and air, and the soil exposure pathway will be discussed in this section. Based on the analytical results noted in the previous section, and the finding from previous investigations, only the groundwater pathway appears to be subject to a release from the site. It is yet to be determined whether Warzyn's analytical data will be HRS useable, in any case, the General hydraulics site does have the potential to effect human health.

### 5.2 GROUNDWATER PATHWAY

The alluvial deposits in the South Beloit area range from less than 30 feet on the west side of the Rock River to more than 225 feet on the east side of the river. The varying depths of the unconsolidated clay, silt, sand, gravel and boulder deposits is due to the buried channel of the Rock Valley and associated bedrock valleys (ISGS, 1960). The unconsolidated deposits are underlain by the Galena-Platteville dolomite, St. Peter sandstone, Trempealeau dolomite, Franconia Formation (interbedded shale, sandstone and dolomite), Iron-ton-Galesville sandstone, Eau Claire Formation (green to red shale, with interbedded dolomite and sandstone) and the Mt. Simon sandstone (ISGS, 1960).

Private wells obtain water primarily from the shallow sand and gravel deposits or the dolomite aquifer in areas where the unconsolidated deposits are thin. Public water supply systems (Table 5-1 lists the Public Water Supply wells within four miles of the site) in the area use a combination of sand and gravel wells with bedrock wells. The closest private wells are along Hayes Avenue. The closest public water supply well is 2000 feet east of the site and is part of the South Beloit-Beloit, Wisconsin public water supply system (owned by the Wisconsin Power and Light Company 500 Townline, Beloit, Wisconsin 53511). Table 5-2 lists distance rings, number of private wells, number of public wells and the total population for all people using groundwater.

Table 5-1

**Public Wells within Four Miles**

<u>Distance</u>	<u>Well Owner</u>	<u>Well</u>	<u>Feet</u>	<u>Aquifer</u>
0.20 mi E	WI Power & Light Co.	#3	1190	Sandstone
0.68 mi NE	WI Power & Light Co.	#10	113	Sand & Gravel
1.33 mi NE	WI Power & Light Co.	#8	140	Sand & Gravel
1.40 mi N	WI Power & Light Co.	#5	1200	Sandstone
2.46 mi SSE	Goldie Floberg	#1	85	Sand & Gravel
2.46 mi SSE	Goldie Floberg	#2	95	Sand & Gravel
2.46 mi SSW	City of Rockton	#5	120	Sand & Gravel
3.03 mi NE	WI Power & Light Co.	#9	1130	Sandstone
3.26 mi ENE	WI Power & Light Co.	#12	107	Sand & Gravel
3.71 mi SSW	City of Rockton	#6	725	Sandstone
3.75 mi NNE	WI Power & Light Co.	#11	149	Sand & Gravel

Table 5-2

**Total Population on Private and Public Wells**

<u>Distance</u>	<u>Private Wells</u>	<u>Public Wells</u>	<u>Total Population</u>
0-1/4	20	1	4153
1/4-1/2	8	0	21
1/2-1	34	1	7271
1-2	251	2	11933
2-3	297	3	2035
3-4	391	4	19134

\*Total population is the total served by public and private well systems. The private wells were multiplied by 2.61 people per household for Winnebago County (Illinois) and 2.68 for Rock County (Wisconsin).

**5.3 SURFACE WATER PATHWAY**

Rain water from the site's relatively flat surface, drains east, emptying into the Rock River. The Rock River is used for recreation (swimming, boating, skiing, canoeing) and fishing for such species as largemouth bass, smallmouth bass, bluegill, crappie, sunfish, northern pike, channel catfish, carp, walleye and bullheads. According to the U.S. Geological Survey Water Data Report (Volume 1, page 148), the Rock River has a drainage area of 6,363 square miles and an average discharge or flow rate of 4,073 cubic feet per second. (All measurements were collected at the Rockton, Illinois gaging station [ID # 05437500] approximately 5 miles downstream from the site). The site is located within the 100 year flood zone and may be within the 10 year flood zone (Federal Emergency Management Agency Flood

Insurance Map for South Beloit, Illinois). Wetland areas occur along a major portion of the surface water route throughout the fifteen miles downstream. According to the Illinois Department of Conservation, (with the exception of wetlands) there are no sensitive environments located within a one mile radius of the site. Also, there are no known sensitive aquatic species which occur along the fifteen mile downstream surface water route.

#### 5.4 AIR PATHWAY

The smell of styrene (from Accra Plastics) was obnoxious while sampling the private wells during the second day of CERCLA SSI. Some of the Hayes Avenue residents have complained about the smell to local authorities.

Wind blown across the uncovered contaminated soil pile could spread the contamination. The rest of the site is either vegetated or under some type of cover material.

It has been estimated that about 11,500 people live within a mile of the site and about 45,000 people live within 4-miles, based on 1990 U.S. Census figures. Table 5-3 shows the 4-mile radius population calculation.

Table 5-3

**Target Population Calculation**

<u>City</u>	<u>Population Density/ Total Population</u>	<u>Area w/in 4- Mile Radius</u>	<u>Population w/in 4-Mile Radius</u>
S. Beloit	4,088	100 %	4,088
Beloit, WI	35,729	100 %	35,729
Rockton	2,313	100 %	2,313
rural	2.64/house	1000 homes	2,640

Total Target Population = 44,770

**5.5 SOIL EXPOSURE PATHWAY**

The off-site soil sample collected at St. Peters school yard indicates that the contamination has not migrated to this point. For the most part, General Hydraulics is covered with vegetation and asphalt, so it is unlikely that wind blown soils have migrated to the nearby residential area. Only the uncovered, contaminated soil pile on-site, poses a threat of soil exposure. The site is not fenced and there may be an attractiveness for kids to play on the soil pile.

## 6. BIBLIOGRAPHY

Bureau of the Census. County and City Data Book. 1990 U.S. Census data.

Federal Emergency Management Agency, Revised May 1, 1984, Flood Insurance Map for the City of South Beloit, Illinois.

Illinois Department of Energy and Natural Resources, 1984, Geology for Planning in Boone and Winnebago Counties, 69p.

Illinois Department of Transportation aerial photographs, Bureau of Location and Environment, Aerial Survey Section, aerial photos from 1964, 1978 and 1988.

Illinois Environmental Protection Agency Division of Land Pollution Control, file for General Hydraulics, L201045022.

Illinois Environmental Protection Agency Division of Public Water Supplies, July 1990, Groundwater Quality Protection Program, Well Site Survey for the City of South Beloit ID # 2010450.

Illinois State Geological Survey, 1960, Ground-Water Geology of Winnebago County, Illinois, Report of Investigations 213, 63p.

Illinois State Water Survey, well logs for T.46N. R.2E. and T.46N. R.1E.

Lutz, Richard W., Illinois Department of Conservation, Division of Planning, Impact Analysis Section Supervisor, April 29, 1991 correspondence.

Winnebago County Tax Assessors Office, 400 West State Street, Rockford, Illinois, ownership check on General Hydraulics parcels.

U.S. Department of the Interior. Water Resources Data Illinois, Water Year 1989 Volume 1. Illinois except Illinois River Basin. U.S. Geological Survey, 1990

U.S. Department of the Interior. Fish and Wildlife Service, National Wetlands Inventory Maps: 1987, South Beloit, Ill-Wis. Quadrangle (12A)

U.S. Geological Survey, 1976, Beloit, Wis. Quadrangle (unk #) 1976, Shopiere, Wis. Quadrangle (unk #), 1976, South Beloit, Ill-Wis. Quadrangle (12A), 1975, Belvidere, Ill-Wis. Quadrangle (11B), 7.5 Minute Series

## 6. BIBLIOGRAPHY

Bureau of the Census. County and City Data Book. 1990 U.S. Census data.

Federal Emergency Management Agency, Revised May 1, 1984, Flood Insurance Map for the City of South Beloit, Illinois.

Illinois Department of Energy and Natural Resources, 1984, Geology for Planning in Boone and Winnebago Counties, 69p.

Illinois Department of Transportation aerial photographs, Bureau of Location and Environment, Aerial Survey Section, aerial photos from 1964, 1978 and 1988.

Illinois Environmental Protection Agency Division of Land Pollution Control, file for General Hydraulics, L201045022.

Illinois Environmental Protection Agency Division of Public Water Supplies, July 1990, Groundwater Quality Protection Program, Well Site Survey for the City of South Beloit ID # 2010450.

Illinois State Geological Survey, 1960, Ground-Water Geology of Winnebago County, Illinois, Report of Investigations 213, 63p.

Illinois State Water Survey, well logs for T.46N. R.2E. and T.46N. R.1E.

Lutz, Richard W., Illinois Department of Conservation, Division of Planning, Impact Analysis Section Supervisor, April 29, 1991 correspondence.

Winnebago County Tax Assessors Office, 400 West State Street, Rockford, Illinois, ownership check on General Hydraulics parcels.


U.S. Department of the Interior. Water Resources Data Illinois, Water Year 1989 Volume 1. Illinois except Illinois River Basin. U.S. Geological Survey, 1990

U.S. Department of the Interior. Fish and Wildlife Service, National Wetlands Inventory Maps: 1987, South Beloit, Ill-Wis. Quadrangle (12A)

U.S. Geological Survey, 1976, Beloit, Wis. Quadrangle (unk #) 1976, Shopiere, Wis. Quadrangle (unk #), 1976, South Beloit, Ill-Wis. Quadrangle (12A), 1975, Belvidere, Ill-Wis. Quadrangle (11B), 7.5 Minute Series

APPENDIX A  
GROUNDWATER 4-MILE RADIUS MAP





ILLINOIS ENVIRONMENTAL PROTECTION AGENCY		SITE: General Hydraulics SITE ILD 984767806	
USGS TOPOGRAPHIC MAPS		Site Location	
NAME: Beloit, Wis.	NAME: Shopiere, Wis.	Nearest Private Well	
NUMBER: unk.	NUMBER: unk.	●	
DATE: 1976	DATE: 1976	Municipal Bdy.	
		Public Wells	
		▲	
NAME: South Beloit, Ill.-Wis.	NAME: Belvidere, Ill.-Wis.	ILLINOIS	
NUMBER: 12A	NUMBER: 11B	QUADRANGLE LOCATION	
DATE: 1976	DATE: 1975		
SCALE 1:24 000		1 MILE	
1 1000 0 1000 2000 3000 4000 5000 6000 7000 FEET		N W E S	
1 5 0 5 10 KILOMETER			
CONTOUR INTERVAL 10 FEET			



APPENDIX B  
SURFACE WATER ROUTE MAP



**SOUTH BELOIT, ILL. - WIS.**

**MOIS ENVIRONMENTAL  
TECTION AGENCY**

**SITE: General Hydraulics  
SITE ILD 984767806**

**outh Beloit, Ill-  
Wis.  
12A  
987**

**ockford North, Ill  
12D  
987**

**N**  
**W E S**

**15-MILE SURFACE WATER MAP  
NATIONAL WETLAND INVENTORY MAPS**

<b>Site Location</b>	<b>15 Mile End</b>	<b>Surface Water Intake</b>
[Symbol]	[Symbol]	[Symbol]

Surface Water  
Intake

**SYSTEM**

**M - MARINE**

**SUBSYSTEM**

**CLASS**

**1 - SUBTIDAL**

**2 - INTERTIDAL**

**3 - EBB FLAT**

**4 - FLOOD FLAT**

**5 - SHALLOW BAY**

**6 - DEEP BAY**

**7 - OPEN WATER**

**8 - ROCK BOTTOM**

**9 - UNCONSOLIDATED BOTTOM**

**10 - AQUATIC BED**

**11 - REEF**

**12 - OPEN WATER**

**13 - AQUATIC BED**

**14 - REEF**

**15 - ROCK BOTTOM**

**16 - UNCONSOLIDATED BOTTOM**

**17 - AQUATIC BED**

**18 - REEF**

**19 - OPEN WATER**

**20 - AQUATIC BED**

**21 - REEF**

**22 - OPEN WATER**

**23 - AQUATIC BED**

**24 - REEF**

**25 - OPEN WATER**

**26 - AQUATIC BED**

**27 - REEF**

**28 - OPEN WATER**

**29 - AQUATIC BED**

**30 - REEF**

**31 - OPEN WATER**

**32 - AQUATIC BED**

**33 - REEF**

**34 - OPEN WATER**

**35 - AQUATIC BED**

**36 - REEF**

**37 - OPEN WATER**

**38 - AQUATIC BED**

**39 - REEF**

**40 - OPEN WATER**

**41 - AQUATIC BED**

**42 - REEF**

**43 - OPEN WATER**

**44 - AQUATIC BED**

**45 - REEF**

**46 - OPEN WATER**

**47 - AQUATIC BED**

**48 - REEF**

**49 - OPEN WATER**

**50 - AQUATIC BED**

**51 - REEF**

**52 - OPEN WATER**

**53 - AQUATIC BED**

**54 - REEF**

**55 - OPEN WATER**

**56 - AQUATIC BED**

**57 - REEF**

**58 - OPEN WATER**

**59 - AQUATIC BED**

**60 - REEF**

**61 - OPEN WATER**

**62 - AQUATIC BED**

**63 - REEF**

**64 - OPEN WATER**

**65 - AQUATIC BED**

**66 - REEF**

**67 - OPEN WATER**

**68 - AQUATIC BED**

**69 - REEF**

**70 - OPEN WATER**

**71 - AQUATIC BED**

**72 - REEF**

**73 - OPEN WATER**

**74 - AQUATIC BED**

**75 - REEF**

**76 - OPEN WATER**

**77 - AQUATIC BED**

**78 - REEF**

**79 - OPEN WATER**

**80 - AQUATIC BED**

**81 - REEF**

**82 - OPEN WATER**

**83 - AQUATIC BED**

**84 - REEF**

**85 - OPEN WATER**

**86 - AQUATIC BED**

**87 - REEF**

**88 - OPEN WATER**

**89 - AQUATIC BED**

**90 - REEF**

**91 - OPEN WATER**

**92 - AQUATIC BED**

**93 - REEF**

**94 - OPEN WATER**

**95 - AQUATIC BED**

**96 - REEF**

**97 - OPEN WATER**

**98 - AQUATIC BED**

**99 - REEF**

**100 - OPEN WATER**

**101 - AQUATIC BED**

**102 - REEF**

**103 - OPEN WATER**

**104 - AQUATIC BED**

**105 - REEF**

**106 - OPEN WATER**

**107 - AQUATIC BED**

**108 - REEF**

**109 - OPEN WATER**

**110 - AQUATIC BED**

**111 - REEF**

**112 - OPEN WATER**

**113 - AQUATIC BED**

**114 - REEF**

**115 - OPEN WATER**

**116 - AQUATIC BED**

**117 - REEF**

**118 - OPEN WATER**

**119 - AQUATIC BED**

**120 - REEF**

**121 - OPEN WATER**

**122 - AQUATIC BED**

**123 - REEF**

**124 - OPEN WATER**

**125 - AQUATIC BED**

**126 - REEF**

**127 - OPEN WATER**

**128 - AQUATIC BED**

**129 - REEF**

**130 - OPEN WATER**

**131 - AQUATIC BED**

**132 - REEF**

**133 - OPEN WATER**

**134 - AQUATIC BED**

**135 - REEF**

**136 - OPEN WATER**

**137 - AQUATIC BED**

**138 - REEF**

**139 - OPEN WATER**

**140 - AQUATIC BED**

**141 - REEF**

**142 - OPEN WATER**

**143 - AQUATIC BED**

**144 - REEF**

**145 - OPEN WATER**

**146 - AQUATIC BED**

**147 - REEF**

**148 - OPEN WATER**

**149 - AQUATIC BED**

**150 - REEF**

**151 - OPEN WATER**

**152 - AQUATIC BED**

**153 - REEF**

**154 - OPEN WATER**

**155 - AQUATIC BED**

**156 - REEF**

**157 - OPEN WATER**

**158 - AQUATIC BED**

**159 - REEF**

**160 - OPEN WATER**

**161 - AQUATIC BED**

**162 - REEF**

**163 - OPEN WATER**

**164 - AQUATIC BED**

**165 - REEF**

**166 - OPEN WATER**

**167 - AQUATIC BED**

**168 - REEF**

**169 - OPEN WATER**

**170 - AQUATIC BED**

**171 - REEF**

**172 - OPEN WATER**

**173 - AQUATIC BED**

**174 - REEF**

**175 - OPEN WATER**

**176 - AQUATIC BED**

**177 - REEF**

**178 - OPEN WATER**

**179 - AQUATIC BED**

**180 - REEF**

**181 - OPEN WATER**

**182 - AQUATIC BED**

**183 - REEF**

**184 - OPEN WATER**

**185 - AQUATIC BED**

**186 - REEF**

**187 - OPEN WATER**

**188 - AQUATIC BED**

**189 - REEF**

**190 - OPEN WATER**

**191 - AQUATIC BED**

**192 - REEF**

**193 - OPEN WATER**

**194 - AQUATIC BED**

**195 - REEF**

**196 - OPEN WATER**

**197 - AQUATIC BED**

**198 - REEF**

**199 - OPEN WATER**

**200 - AQUATIC BED**

**201 - REEF**

**202 - OPEN WATER**

**203 - AQUATIC BED**

**204 - REEF**

**205 - OPEN WATER**

**206 - AQUATIC BED**

**207 - REEF**

**208 - OPEN WATER**

**209 - AQUATIC BED**

**210 - REEF**

**211 - OPEN WATER**

**212 - AQUATIC BED**

**213 - REEF**

**214 - OPEN WATER**

**215 - AQUATIC BED**

**216 - REEF**

**217 - OPEN WATER**

**218 - AQUATIC BED**

**219 - REEF**

**220 - OPEN WATER**

**221 - AQUATIC BED**

**222 - REEF**

**223 - OPEN WATER**

**224 - AQUATIC BED**

**225 - REEF**

**226 - OPEN WATER**

**227 - AQUATIC BED**

**228 - REEF**

**229 - OPEN WATER**

**230 - AQUATIC BED**

**231 - REEF**

**232 - OPEN WATER**

**233 - AQUATIC BED**

**234 - REEF**

**235 - OPEN WATER**

**236 - AQUATIC BED**

**237 - REEF**

**238 - OPEN WATER**

**239 - AQUATIC BED**

**240 - REEF**

**241 - OPEN WATER**

**242 - AQUATIC BED**

**243 - REEF**

**244 - OPEN WATER**

**245 - AQUATIC BED**

**246 - REEF**

**247 - OPEN WATER**

**248 - AQUATIC BED**

**249 - REEF**

**250 - OPEN WATER**

**251 - AQUATIC BED**

**252 - REEF**



# SDMS US EPA Region V

## *Imagery Insert Form*

**Some images in this document may be illegible or unavailable in SDMS.  
Please see reason(s) indicated below:**

☐

Illegible due to bad source documents. Image(s) in SDMS is equivalent to hard copy.

**Specify Type of Document(s) / Comment**

☐

**Confidential Business Information (CBI).**

This document contains highly sensitive information. Due to confidentiality, materials with such information are not available in SDMS. You may contact the EPA Superfund Records Manager if you wish to view this document.

**Specify Type of Document(s) / Comment**

☐

**Unscannable Material: Oversized \_\_\_\_ or \_\_\_\_ Format.**

Due to certain scanning equipment capability limitations, the document page(s) is not available in SDMS. The original document is available for viewing at the Superfund Records center.

**Specify Type of Document(s) / Comment**

☐

**Other:**

APPENDIX C  
USEPA FORM 2070-13

L2010450022/Winnebago Co.  
General Hydraulics  
ILD 984767806



# Site Inspection Report



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 1 - SITE LOCATION AND INSPECTION INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 984767806

II. SITE NAME AND LOCATION

01 SITE NAME (Legal, common, or descriptive name of site) General Hydraulics		02 STREET, ROUTE NO., OR SPECIFIC LOCATION IDENTIFIER 301 Charles Ave			
03 CITY South Beloit	04 STATE IL	05 ZIP CODE 61080	06 COUNTY Winnebago	07 COUNTY CODE 201	08 CONG DIST 16
09 COORDINATES LATITUDE 42 29 00.0 LONGITUDE 089 02 30.0		10 TYPE OF OWNERSHIP (Check one) <input checked="" type="checkbox"/> A. PRIVATE <input type="checkbox"/> B. FEDERAL <input type="checkbox"/> C. STATE <input type="checkbox"/> D. COUNTY <input type="checkbox"/> E. MUNICIPAL <input type="checkbox"/> F. OTHER <input type="checkbox"/> G. UNKNOWN			

III. INSPECTION INFORMATION

01 DATE OF INSPECTION 11 / 56 / 91 MONTH DAY YEAR	02 SITE STATUS <input checked="" type="checkbox"/> ACTIVE <input type="checkbox"/> INACTIVE	03 YEARS OF OPERATION early 1950's - 1983* BEGINNING YEAR ENDING YEAR
04 AGENCY PERFORMING INSPECTION (Check all that apply) <input type="checkbox"/> A. EPA <input type="checkbox"/> B. EPA CONTRACTOR <input type="checkbox"/> C. MUNICIPAL <input type="checkbox"/> D. MUNICIPAL CONTRACTOR <input checked="" type="checkbox"/> E. STATE <input type="checkbox"/> F. STATE CONTRACTOR <input type="checkbox"/> G. OTHER		

05 CHIEF INSPECTOR Tim Murphy	06 TITLE EPS	07 ORGANIZATION IEPA	08 TELEPHONE NO. (217) 782-6760
09 OTHER INSPECTORS Al Kirwan	10 TITLE EPS	11 ORGANIZATION IEPA	12 TELEPHONE NO. (309) 693-5463
Greg Spencer	EPS	IEPA	(217) 782-6760
Bruce Ford	EPE	IEPA	(217) 782-6760
			( )
			( )

13 SITE REPRESENTATIVES INTERVIEWED Roger Taylor - NATCo	14 TITLE Pres.	15 ADDRESS S. Beloit, IL 61080 215 Elmwood Ave.	16 TELEPHONE NO. (815) 389-2300
Curt Lansbury - NATCo	V.P.	11	( ) 11
Burk Griessler - NATCo	attorney		( )
Dave Saunders - Trenwyth Ind.		S. Beloit, IL 61080 208 Charles Ave.	(815) 389-3003
Cy Hotek - Trenwyth Ind.		11	( ) 11
John Wihlborg - Accra Plastics		S. Beloit, IL 61080 238 Charles Ave.	(815) 389-5100


17 ACCESS GAINED BY (Check one) <input checked="" type="checkbox"/> PERMISSION <input type="checkbox"/> WARRANT	18 TIME OF INSPECTION 12:30pm	19 WEATHER CONDITIONS cold 29° F overcast w/ light snow
---	----------------------------------	--

IV. INFORMATION AVAILABLE FROM

01 CONTACT	02 OF (Agency/Organization)		03 TELEPHONE NO. ( )	
04 PERSON RESPONSIBLE FOR SITE INSPECTION FORM Tim Murphy	05 AGENCY IEPA	06 ORGANIZATION BLP/DRM/RPM	07 TELEPHONE NO. (217) 524-1657	08 DATE 6 / 2 / 92 MONTH DAY YEAR

EPA FORM 2070-13 (7-81)

\* New facilities have moved into the parcelled property

[illegible]





POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
ILD 984767806

II. HAZARDOUS CONDITIONS AND INCIDENTS

01 ☒ A. GROUNDWATER CONTAMINATION 02 ☒ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: 744,000 04 NARRATIVE DESCRIPTION

Two of four GW monitor wells have shown concentrations of PCE at 5.8 ug/l (ppb) in G101 and 4.8 ug/l (ppb) in G104

01 ☒ B. SURFACE WATER CONTAMINATION 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

Site is 450' E of Rock River however, the drainage pathway for the site was sampled and it does not appear the river has been impacted via overland route

01 ☒ C. CONTAMINATION OF AIR 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

Uncovered pile of contaminated soil may release very low levels of volatiles  
Soil gas readings were obtained (of the compounds found in Part 2 IV) in Aug. 90

01 ☐ D. FIRE/EXPLOSIVE CONDITIONS 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_ 04 NARRATIVE DESCRIPTION

NONE documented or observed

01 ☒ E. DIRECT CONTACT 02 ☐ OBSERVED (DATE: \_\_\_\_\_) ☒ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: 4088 04 NARRATIVE DESCRIPTION

No contamination was found off-site however the on-site contaminated soil pile is uncovered and site access is NOT controlled

01 ☒ F. CONTAMINATION OF SOIL 02 ☒ OBSERVED (DATE: 5-16-86 \*) ☐ POTENTIAL ☐ ALLEGED  
03 AREA POTENTIALLY AFFECTED: 8 (Acres) 04 NARRATIVE DESCRIPTION

Samples collected by NATCO contractor 9-10-90 showed contaminants listed on previous page Part 2 IV in Sept. 1990

01 ☒ G. DRINKING WATER CONTAMINATION 02 ☒ OBSERVED (DATE: 6-23-86 ) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: 744,000 04 NARRATIVE DESCRIPTION

Two of nine homes sampled on either side of Hayes Ave (adjacent the site) were found to have PCE at 7 ug/l (ppb) during SSI

01 ☒ H. WORKER EXPOSURE/INJURY 02 ☒ OBSERVED (DATE: 6-23-86 ) ☐ POTENTIAL ☐ ALLEGED  
03 WORKERS POTENTIALLY AFFECTED: 50 04 NARRATIVE DESCRIPTION

50 workers (on-site) at Trenwyth Ind. were drinking contaminated well water 1.8 ug/l (ppb) PCE prior to the addition of a charcoal filtering system.  
1.3 ug/l (ppb) PCE found at Hanson General Products (on-site) 12-21-87 w/ 10-15 employees (Accra Plastics)

01 ☒ I. POPULATION EXPOSURE/INJURY 02 ☒ OBSERVED (DATE: \_\_\_\_\_) ☐ POTENTIAL ☐ ALLEGED  
03 POPULATION POTENTIALLY AFFECTED: 744,000 04 NARRATIVE DESCRIPTION

See E. G. + H. above



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 3 - DESCRIPTION OF HAZARDOUS CONDITIONS AND INCIDENTS

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 984767806

II. HAZARDOUS CONDITIONS AND INCIDENTS (Continued)

01 ☐ J. DAMAGE TO FLORA  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☐ K. DAMAGE TO FAUNA  
04 NARRATIVE DESCRIPTION (Include name(s) of species)

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☐ L. CONTAMINATION OF FOOD CHAIN  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☒ M. UNSTABLE CONTAINMENT OF WASTES  
(Spills/Runoff/Standing liquids, Leaking drums)

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

03 POPULATION POTENTIALLY AFFECTED: \_\_\_\_\_

04 NARRATIVE DESCRIPTION

Pile of contaminated soil need to be disposed of

01 ☐ N. DAMAGE TO OFFSITE PROPERTY  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☐ O. CONTAMINATION OF SEWERS, STORM DRAINS, WWTPs  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

01 ☐ P. ILLEGAL/UNAUTHORIZED DUMPING  
04 NARRATIVE DESCRIPTION

02 ☐ OBSERVED (DATE: \_\_\_\_\_)

☐ POTENTIAL

☐ ALLEGED

None documented or observed

05 DESCRIPTION OF ANY OTHER KNOWN, POTENTIAL, OR ALLEGED HAZARDS

III. TOTAL POPULATION POTENTIALLY AFFECTED: 744,000

IV. COMMENTS

V. SOURCES OF INFORMATION (Cite specific references, e. g., state files, sample analysis, reports)

IEPA BLPC file L201045022

90SI NATCo

Site Reconnaissance 10/22/91



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION  
PART 4 - PERMIT AND DESCRIPTIVE INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
ILD 984767806

II. PERMIT INFORMATION

01 TYPE OF PERMIT ISSUED (Check all that apply)	02 PERMIT NUMBER	03 DATE ISSUED	04 EXPIRATION DATE	05 COMMENTS
<input type="checkbox"/> A. NPDES				
<input type="checkbox"/> B. UIC				
<input checked="" type="checkbox"/> C. AIR	201045A88 88070083	Sept '88	wrk	at Accra Plastics (Styrene)
<input checked="" type="checkbox"/> D. RCRA	ILD151870409	April '89	wrk	NATCo (Small quantity)
<input checked="" type="checkbox"/> E. RCRA INTERIM STATUS	ILD102372315	Sept '88	wrk	Accra Plastics (Small quantity)
<input type="checkbox"/> F. SPCC PLAN				
<input type="checkbox"/> G. STATE (Specify)				
<input type="checkbox"/> H. LOCAL (Specify)				
<input type="checkbox"/> I. OTHER (Specify)				
<input type="checkbox"/> J. NONE				

III. SITE DESCRIPTION

01 STORAGE/DISPOSAL (Check all that apply)	02 AMOUNT	03 UNIT OF MEASURE	04 TREATMENT (Check all that apply)	05 OTHER
<input type="checkbox"/> A. SURFACE IMPOUNDMENT			<input type="checkbox"/> A. INCENERATION	<input checked="" type="checkbox"/> A. BUILDINGS ON SITE
<input checked="" type="checkbox"/> B. PILES	3,870	ft <sup>3</sup>	<input type="checkbox"/> B. UNDERGROUND INJECTION	
<input type="checkbox"/> C. DRUMS, ABOVE GROUND			<input type="checkbox"/> C. CHEMICAL/PHYSICAL	
<input type="checkbox"/> D. TANK, ABOVE GROUND			<input type="checkbox"/> D. BIOLOGICAL	
<input type="checkbox"/> E. TANK, BELOW GROUND			<input type="checkbox"/> E. WASTE OIL PROCESSING	
<input type="checkbox"/> F. LANDFILL			<input type="checkbox"/> F. SOLVENT RECOVERY	06 AREA OF SITE
<input type="checkbox"/> G. LANDFARM			<input type="checkbox"/> G. OTHER RECYCLING/RECOVERY	8 (Acres)
<input type="checkbox"/> H. OPEN DUMP			<input type="checkbox"/> H. OTHER (Specify)	
<input type="checkbox"/> I. OTHER (Specify)				

07 COMMENTS

The pile comes from under the new addition to NATC (excavation size 43'x18'x5' = 3870 ft<sup>3</sup>). As the soils were removed, the soil in each backhoe was screened with an HNu PID (11.7eV). Soils with readings above background were segregated and piled on-site.

IV. CONTAINMENT

01 CONTAINMENT OF WASTES (Check one)  
☐ A. ADEQUATE, SECURE ☐ B. MODERATE ☒ C. INADEQUATE, POOR ☐ D. INSECURE, UNSOUND, DANGEROUS

02 DESCRIPTION OF DRUMS, DIKING, LINERS, BARRIERS, ETC.

Contaminated Soil stockpiled on plastic

V. ACCESSIBILITY

01 WASTE EASILY ACCESSIBLE: ☒ YES ☐ NO  
02 COMMENTS

VI. SOURCES OF INFORMATION (Cite specific references, e.g. state files, sample analysis, reports)

Site Reconnaissance 10/22/91



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
ILD 984767806

II. DRINKING WATER SUPPLY

01 TYPE OF DRINKING SUPPLY  
(Check as applicable)

SURFACE WELL  
COMMUNITY A. ☐ B. ☒  
NON-COMMUNITY C. ☐ D. ☒

02 STATUS

ENDANGERED AFFECTED MONITORED  
A. ☒ B. ☐ C. ☐  
D. ☐ E. ☒ F. ☐

03 DISTANCE TO SITE

A. .2 (mi)  
B. .009 (mi)

III. GROUNDWATER

01 GROUNDWATER USE IN VICINITY (Check one)

☒ A. ONLY SOURCE FOR DRINKING ☐ B. DRINKING  
(Other sources available)  
COMMERCIAL, INDUSTRIAL, IRRIGATION  
(No other water sources available)  
☐ C. COMMERCIAL, INDUSTRIAL, IRRIGATION  
(Limited other sources available)  
☐ D. NOT USED, UNUSEABLE

02 POPULATION SERVED BY GROUND WATER >44,000

03 DISTANCE TO NEAREST DRINKING WATER WELL .009 (mi)

04 DEPTH TO GROUNDWATER

6-7 (ft)

05 DIRECTION OF GROUNDWATER FLOW

UNK possibly W-SW

06 DEPTH TO AQUIFER  
OF CONCERN

6 (ft)

07 POTENTIAL YIELD  
OF AQUIFER

UNK (gpd)

08 SOLE SOURCE AQUIFER

☐ YES ☒ NO

09 DESCRIPTION OF WELLS (Including usage, depth, and location relative to population and buildings)

ON-site wells are 15 feet deep, nearby, residential wells are less than 20 feet deep,  
The public well in bedrock (open from 230.5 - 1185 feet).

10 RECHARGE AREA

☒ YES COMMENTS  
☐ NO

fill/alluvial deposits

11 DISCHARGE AREA

☒ YES COMMENTS  
☐ NO

Rock River

IV. SURFACE WATER

01 SURFACE WATER USE (Check one)

☒ A. RESERVOIR, RECREATION  
DRINKING WATER SOURCE ☐ B. IRRIGATION, ECONOMICALLY  
IMPORTANT RESOURCES ☐ C. COMMERCIAL, INDUSTRIAL ☐ D. NOT CURRENTLY USED

02 AFFECTED/POTENTIALLY AFFECTED BODIES OF WATER

NAME:

Rock River

AFFECTED

DISTANCE TO SITE

.085 (mi)

V. DEMOGRAPHIC AND PROPERTY INFORMATION

01 TOTAL POPULATION WITHIN

ONE (1) MILE OF SITE  
A. 11,500  
NO. OF PERSONS

TWO (2) MILES OF SITE  
B. 25,000  
NO. OF PERSONS

THREE (3) MILES OF SITE  
C. 40,000  
NO. OF PERSONS

02 DISTANCE TO NEAREST POPULATION

.009 (mi)

03 NUMBER OF BUILDINGS WITHIN TWO (2) MILES OF SITE

10,000

04 DISTANCE TO NEAREST OFF-SITE BUILDING

.009 (mi)

05 POPULATION WITHIN VICINITY OF SITE (Provide narrative description of nature of population within vicinity of site, e.g., rural, village, densely populated urban area)

South Beloit 4088, Beloit has 40,000 - two cities near site with average  
densities, the surrounding rural areas are fairly populated.



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 5 - WATER, DEMOGRAPHIC, AND ENVIRONMENTAL DATA

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 984767806

VI. ENVIRONMENTAL INFORMATION

01 PERMEABILITY OF UNSATURATED ZONE (Check one)

☐ A.  $10^{-8}$  -  $10^{-8}$  cm/sec ☐ B.  $10^{-4}$  -  $10^{-6}$  cm/sec ☒ C.  $10^{-4}$  -  $10^{-3}$  cm/sec ☐ D. GREATER THAN  $10^{-3}$  cm/sec

02 PERMEABILITY OF BEDROCK (Check one)

☐ A. IMPERMEABLE (Less than  $10^{-6}$  cm/sec) ☐ B. RELATIVELY IMPERMEABLE ( $10^{-4}$  -  $10^{-6}$  cm/sec) ☒ C. RELATIVELY PERMEABLE ( $10^{-2}$  -  $10^{-4}$  cm/sec) ☐ D. VERY PERMEABLE (Greater than  $10^{-2}$  cm/sec)

03 DEPTH TO BEDROCK

73 (ft)

04 DEPTH OF CONTAMINATED SOIL ZONE

>5 (ft)

05 SOIL pH

UNK

06 NET PRECIPITATION

35 (in)

07 ONE YEAR 24 HOUR RAINFALL

2.5 (in)

08 SLOPE  
SITE SLOPE

0 %

DIRECTION OF SITE SLOPE

W

TERRAIN AVERAGE SLOPE

<2 %

09 FLOOD POTENTIAL

SITE IS IN 100 YEAR FLOODPLAIN

10

☐ SITE IS ON BARRIER ISLAND, COASTAL HIGH HAZARD AREA, RIVERINE FLOODWAY

11 DISTANCE TO WETLANDS (5 acre minimum)

ESTUARINE

OTHER

A. (mi)

B. .056 (mi)

12 DISTANCE TO CRITICAL HABITAT (of endangered species)

NA (mi)

ENDANGERED SPECIES:

13 LAND USE IN VICINITY

DISTANCE TO:

COMMERCIAL/INDUSTRIAL

RESIDENTIAL AREAS; NATIONAL/STATE PARKS,  
FORESTS, OR WILDLIFE RESERVES

AGRICULTURAL LANDS  
PRIME AG LAND AG LAND

A. 0 (mi)

B. 0 (mi)

C. (mi) D. (mi)

14 DESCRIPTION OF SITE IN RELATION TO SURROUNDING TOPOGRAPHY

See maps in appendix A + B in report

VII. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

USGS Topographic Maps  
National Wetlands Inventory Maps



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 6 - SAMPLE AND FIELD INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
ILD 984767806

II. SAMPLES TAKEN

SAMPLE TYPE	01 NUMBER OF SAMPLES TAKEN	02 SAMPLES SENT TO	03 ESTIMATED DATE RESULTS AVAILABLE
GROUNDWATER	9	IEPA Springfield lab (organics) Champigny lab (inorganics)	2-92
SURFACE WATER			
WASTE			
AIR			
RUNOFF			
SPILL			
SOIL	7	11	11
VEGETATION			
OTHER			

III. FIELD MEASUREMENTS TAKEN

01 TYPE	02 COMMENTS
temp, sp. cond + pH	for each private well sampled

IV. PHOTOGRAPHS AND MAPS

01 TYPE <input checked="" type="checkbox"/> GROUND <input checked="" type="checkbox"/> AERIAL	02 IN CUSTODY OF <u>IEPA</u> <small>(Name of organization or individual)</small>
03 MAPS <input checked="" type="checkbox"/> YES <input type="checkbox"/> NO	04 LOCATION OF MAPS <u>Appendix A+B in report</u>

V. OTHER FIELD DATA COLLECTED (Provide narrative description)

water levels were collected during site reconnaissance

VI. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

SSI 11/5-6/92



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 7 - OWNER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 984767806

II. CURRENT OWNER(S)				PARENT COMPANY (if applicable)			
01 NAME Accera Plastics		02 D+B NUMBER		08 NAME Hanson General Products Corp.		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 238 Charles Ave.		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.) 238 Charles Ave.		11 SIC CODE	
05 CITY S. Beloit	06 STATE IL	07 ZIP CODE 61080		12 CITY S. Beloit	13 STATE IL	14 ZIP CODE 61080	
01 NAME Trenwyth Midwest Ind.		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 208 Charles Ave.		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY S. Beloit	06 STATE IL	07 ZIP CODE 61080		12 CITY	13 STATE	14 ZIP CODE	
01 NAME North American Tool Corp		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 215 Elmwood Ave		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY S. Beloit	06 STATE IL	07 ZIP CODE 61080		12 CITY	13 STATE	14 ZIP CODE	
01 NAME		02 D+B NUMBER		08 NAME		09 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		10 STREET ADDRESS (P.O. Box, RFD #, etc.)		11 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE		12 CITY	13 STATE	14 ZIP CODE	
III. PREVIOUS OWNER(S) (List most recent first)				IV. REALTY OWNER(S) (if applicable; list most recent first)			
01 NAME General Hydraulics		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.) 301 Charles Ave		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY S. Beloit	06 STATE IL	07 ZIP CODE 61080		05 CITY	06 STATE	07 ZIP CODE	
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE	07 ZIP CODE	
01 NAME		02 D+B NUMBER		01 NAME		02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE		05 CITY	06 STATE	07 ZIP CODE	
V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)							
Site reconnaissance 4/26/90 - 10/22/91							



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 8 - OPERATOR INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 984767806

II. CURRENT OPERATOR (Provide if different from owner)				OPERATOR'S PARENT COMPANY (If applicable)			
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER					
III. PREVIOUS OPERATOR(S) (List most recent first; provide only if different from owner)				PREVIOUS OPERATORS' PARENT COMPANIES (If applicable)			
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
01 NAME		02 D+B NUMBER		10 NAME		11 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)		04 SIC CODE		12 STREET ADDRESS (P.O. Box, RFD #, etc.)		13 SIC CODE	
05 CITY		06 STATE	07 ZIP CODE	14 CITY		15 STATE	16 ZIP CODE
08 YEARS OF OPERATION		09 NAME OF OWNER DURING THIS PERIOD					
IV. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)							
IEPA files L2010456022							





POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 9 - GENERATOR/TRANSPORTER INFORMATION

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 984767806

II. ON-SITE GENERATOR

01 NAME	02 D+B NUMBER	
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	
05 CITY	06 STATE	07 ZIP CODE

III. OFF-SITE GENERATOR(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

IV. TRANSPORTER(S)

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

01 NAME	02 D+B NUMBER	01 NAME	02 D+B NUMBER		
03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE	03 STREET ADDRESS (P.O. Box, RFD #, etc.)	04 SIC CODE		
05 CITY	06 STATE	07 ZIP CODE	05 CITY	06 STATE	07 ZIP CODE

V. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA files LZ010450022



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 984767806

II. PAST RESPONSE ACTIVITIES

01 ☐ A. WATER SUPPLY CLOSED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ B. TEMPORARY WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ C. PERMANENT WATER SUPPLY PROVIDED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ D. SPILLED MATERIAL REMOVED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☒ E. CONTAMINATED SOIL REMOVED

02 DATE 9-10-90

03 AGENCY \_\_\_\_\_

04 DESCRIPTION NATCO removed 3870 ft<sup>3</sup> of contaminated soil from beneath  
there New westward addition

01 ☐ F. WASTE REPACKAGED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☒ G. WASTE DISPOSED ELSEWHERE

02 DATE May 1986

03 AGENCY —

04 DESCRIPTION 112-120 55 gallon drums + 25-50 5 gallon pails were removed by  
Frinks Industrial Waste (FIW) as contracted by the bankruptcy court

01 ☐ H. ON SITE BURIAL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ I. IN SITU CHEMICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ J. IN SITU BIOLOGICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ K. IN SITU PHYSICAL TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ L. ENCAPSULATION  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ M. EMERGENCY WASTE TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ N. CUTOFF WALLS  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ O. EMERGENCY DIKING/SURFACE WATER DIVERSION  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ P. CUTOFF TRENCHES/SUMP  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ Q. SUBSURFACE CUTOFF WALL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 10 - PAST RESPONSE ACTIVITIES

I. IDENTIFICATION

01 STATE 02 SITE NUMBER  
1LD 984767806

II PAST RESPONSE ACTIVITIES (Continued)

01 ☐ R. BARRIER WALLS CONSTRUCTED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ S. CAPPING/COVERING  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ T. BULK TANKAGE REPAIRED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ U. GROUT CURTAIN CONSTRUCTED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ V. BOTTOM SEALED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ W. GAS CONTROL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ X. FIRE CONTROL  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ Y. LEACHATE TREATMENT  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ Z. AREA EVACUATED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ 1. ACCESS TO SITE RESTRICTED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ 2. POPULATION RELOCATED  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

01 ☐ 3. OTHER REMEDIAL ACTIVITIES  
04 DESCRIPTION

02 DATE \_\_\_\_\_

03 AGENCY \_\_\_\_\_

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA BLPc file L2010450022



POTENTIAL HAZARDOUS WASTE SITE  
SITE INSPECTION REPORT  
PART 11 - ENFORCEMENT INFORMATION

I. IDENTIFICATION

01 STATE	02 SITE NUMBER
ILD	984767806

II. ENFORCEMENT INFORMATION

01 PAST REGULATORY/ENFORCEMENT ACTION ☐ YES ☒ NO

02 DESCRIPTION OF FEDERAL, STATE, LOCAL REGULATORY/ENFORCEMENT ACTION

III. SOURCES OF INFORMATION (Cite specific references, e.g., state files, sample analysis, reports)

IEPA BLPC file L2010450022

APPENDIX D  
TARGET COMPOUND LIST

## TARGET COMPOUND LIST

### Volatile Target Compounds

Chloromethane	1,2-Dichloropropane
Bromomethane	cis-1,3-Dichloropropene
Vinyl Chloride	Trichloroethene
Chloroethane	Dibromochloromethane
Methylene Chloride	1,1,2-Trichloroethane
Acetone	Benzene
Carbon Disulfide	trans-1,3-Dichloropropene
1,1-Dichloroethene	Bromoform
1,1-Dichloroethane	4-Methyl-2-pentanone
1,2-Dichloroethene (total)	2-Hexanone
Chloroform	Tetrachloroethene
1,2-Dichloroethane	1,1,2,2-Tetrachloroethane
2-Butanone	Toluene
1,1,1-Trichloroethane	Chlorobenzene
Carbon Tetrachloride	Ethylbenzene
Vinyl Acetate	Styrene
Bromodichloromethane	Xylenes (total)

### Base/Neutral Target Compounds

Hexachloroethane	2,4-Dinitrotoluene
bis(2-Chloroethyl) Ether	Diethylphthalate
Benzyl Alcohol	N-Nitrosodiphenylamine
bis(2-Chloroisopropyl) Ether	Hexachlorobenzene
N-Nitroso-Di-n-Propylamine	Phenanthrene
Nitrobenzene	4-Bromophenyl-phenylether
Hexachlorobutadiene	Anthracene
2-Methylnaphthalene	Di-n-Butylphthalate
1,2,4-Trichlorobenzene	Fluoranthene
Isophorone	Pyrene
Naphthalene	Butylbenzylphthalate
4-Chloroaniline	bis(2-Ethylhexyl) Phthalate
bis(2-chloroethoxy) Methane	Chrysene
Hexachlorocyclopentadiene	Benzo(a) Anthracene
2-Chloronaphthalene	3,3'-Dichlorobenzidene
2-Nitroaniline	Di-n-Octyl Phthalate
Acenaphthylene	Benzo(b) Fluoranthene
3-Nitroaniline	Benzo(k) Fluoranthene
Acenaphthene	Benzo(a) Pyrene
Dibenzofuran	Indeno(1,2,3-cd) Pyrene
Dimethyl Phthalate	Dibenz(a,h) Anthracene
2,6-Dinitrotoluene	Benzo(g,h,i) Perylene
Fluorene	1,2-Dichlorobenzene
4-Nitroaniline	1,3-Dichlorobenzene
4-Chlorophenyl-phenylether	1,4-Dichlorobenzene

### Acid Target Compounds

Benzoic Acid	2,4,6-Trichlorophenol
Phenol	2,4,5-Trichlorophenol
2-Chlorophenol	4-Chloro-3-methylphenol
2-Nitrophenol	2,4-Dinitrophenol
2-Methylphenol	2-Methyl-4,6-dinitrophenol
2,4-Dimethylphenol	Pentachlorophenol
4-Methylphenol	4-Nitrophenol
2,4-Dichlorophenol	

### Pesticide/PCB Target Compounds

alpha-BHC	Endrin Ketone
beta-BHC	Endosulfan Sulfate
delta-BHC	Methoxychlor
gamma-BHC (Lindane)	alpha-Chlorodane
Heptachlor	gamma-Chlorodane
Aldrin	Toxaphene
Heptachlor epoxide	Aroclor-1016
Endosulfan I	Aroclor-1221
4,4'-DDE	Aroclor-1232
Dieldrin	Aroclor-1242
Endrin	Aroclor-1248
4,4'-DDD	Aroclor-1254
Endosulfan II	Aroclor-1260
4,4'-DDT	

### Inorganic Target Compounds

Aluminum	Manganese
Antimony	Mercury
Arsenic	Nickel
Barium	Potassium
Beryllium	Selenium
Cadmium	Silver
Calcium	Sodium
Chromium	Thallium
Cobalt	Vanadium
Copper	Zinc
Iron	Cyanide
Lead	Sulfide
Magnesium	Sulfate

## APPENDIX E

### WELL LOGS



GEOLOGICAL AND WATER SURVEYS WELL RECORD

Completed 10-8-70

Property owner Chas. Fischer Sr. Well No. 1  
Address Blair St. Beloit, Jk.  
Driller Blair License No. 92-285  
Permit No. 9789 Date June 1 70  
Water from Sandstone 13. County Winnebago

at depth 20 to 150 ft.  
Screen: Diam. 1 1/2 in.  
Length: 15 ft. Slot 1/8  
Sec. 1  
Twp. 46 N  
Rge. 1 E  
Elev.     

Casing and Liner Pipe

Diam. (In.)	Kind and Weight	From (Ft.)	To (Ft.)
5	Blk. 1 1/2" 146 Pufft.	0	120

SHOW LOCATION IN SECTION PLAT  
100' NW, 250' E, NW SE  
(permit)

1. Size Hole below casing: 5 in.  
2. Static level 45 ft. below casing top which is 1 ft. above ground level. Pumping level 50 ft. when pumping at 8 gpm for 12 hours.

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Sand	120	120
Sand stone	10	130

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Ralph Blyer DATE Nov. 6-70

COUNTY No. 1562

GEOLOGICAL AND WATER SURVEYS WELL RECORD

Completed 10-11-74

Property owner Ron Swendsen Well No.       
Address 50 Beloit Ill.  
Driller Ed Greenfield License No. 92-582  
Permit No. 93368 Date Sept. 25  
Water from Sandstone 13. County Winnebago

at depth 117 to 127 ft.  
Screen: Diam. 1 1/2 in.  
Length: 10 ft. Slot 1/8  
Sec. 1  
Twp. 46 N  
Rge. 1 E  
Elev.     

Casing and Liner Pipe

Diam. (In.)	Kind and Weight	From (Ft.)	To (Ft.)
4	Blk. PE. 1 1/2" 9.	0	117

SHOW LOCATION IN SECTION PLAT  
100' SL, 100' WL, NW SE NE  
(permit)

16. Size Hole below casing: 4 in.  
17. Static level 80 ft. below casing top which is 1 ft. above ground level. Pumping level 92 ft. when pumping at 20 gpm for 24 hours. Sub. pump set at 105

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
gravel & sand	30	30
clay & gravel	87	117
Sandstone	10	127

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Ed Greenfield DATE Nov. 11

COUNTY No. 23314

GEOLOGICAL AND WATER SURVEYS WELL RECORD

Completed 9-27-74

10. Property owner Steve Namminga Well No. 1  
Address 821 Blackhawk So Beloit, Ill.  
Driller Ed Greenfield License No. 92-582  
1. Permit No. 33369 Date Sept. 25  
2. Water from Sand 13. County Winnebago

at depth 66 to 68 ft. Sec. 7  
4. Screen: Diam. 4 in. Twp. 46N  
Length: 2 ft. Slot 15 Rge. 28  
Elev. \_\_\_\_\_

5. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)	SHOW LOCATION IN SECTION PLAT 50' SL, 50' WL of NE NE SW (Permit)
4	Blk. P.E. 11# ft.	0	66	
4	Johnson S.S. screen	66	68	

6. Size Hole below casing: \_\_\_\_\_ in.  
7. Static level 48 ft. below casing top which is \_\_\_\_\_ ft.  
above ground level. Pumping level 51 ft. when pumping at \_\_\_\_\_  
gpm for \_\_\_\_\_ hours. Submersible, set at 50'

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Sand	68	68

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Ed Greenfield DATE Oct. 7-74  
COUNTY No. 23278

GEOLOGICAL AND WATER SURVEYS WELL RECORD

Completed 7/18/75

10. Property owner George Leonard Well No. \_\_\_\_\_  
Address 442 Whittemore So Beloit  
Driller Ed Greenfield License No. 92-582  
11. Permit No. 39223 Date July 10  
12. Water from Sand 13. County Winnebago

at depth 63 to 65 ft. Sec. 7  
14. Screen: Diam. 4 in. Twp. 46N  
Length: 2 ft. Slot 15 Rge. 28  
Elev. \_\_\_\_\_

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (Ft.)	To (Ft.)	SHOW LOCATION IN SECTION PLAT 50' SL, 50' WL of NE SE SW (permit)
4	Blk. P.E. 11# ft.	0	63	
4	S.S. screen	63	65	

16. Size Hole below casing: \_\_\_\_\_ in.  
17. Static level 50 ft. below casing top which is \_\_\_\_\_ ft.  
above ground level. Pumping level 50 ft. when pumping at \_\_\_\_\_  
gpm for \_\_\_\_\_ hours. Sub. pump set at 55'

FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
Sand + gravel	6	6
Sand	57	65

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Ed Greenfield DATE Aug 1  
COUNTY No. 23613





T. 46N R. 2E S. 5

IPANY C. W. Varner HOLE NO. #3  
M Wisconsin Power & Light-HOLE NO. #3

STRATA	THICKNESS		DEPTH	
	FEET	IN.	FEET	IN.
Lime, blue, sandy	40		925	
Lime, gray, sandy	18		943	
Lime, blue, sandy	5		948	
Shale, brown	3		951	
Lime, gray, hard	4		955	
Dolomite, blue, hard	8		963	
Dolomite, gray, very hard	4		967	
Lime, gray	7		974	
Lime, blue	4		978	
Sand, gray	14		992	
Shale, blue, hard	1		993	
Sand, fine, firm	5		998	
Shale, red, firm	2		1000	
Sand, fine, firm	7		1007	
Lime, red, not very hard	3		1010	
Lime, red, hard	10		1020	
Sand, gray	11		1031	
Sand, fine, red, hard	13		1044	
Sand, gray, fine, hard	31		1075	
Dolomite, gray, hard, fine	7		1082	
Lime, brown, sandy	5		1087	
Red sand, soft to hard, fine	78		1165	
Sand, light red, fine	20		1185	

Diameter: 17" to 352"  
12 3/4" to bottom at 1185"  
Casing: 230'5" of 18" O.D. pipe from surface.

CITY Winnebago INDEX NO. 0105  
ILL. RECORD 5-46N-2E  
50560-15M-8-36 ILLINOIS GEOLOGICAL SURVEY, URBANA

REQUESTED AND MAIL ORIGINAL TO STATE  
BUREAU OF ENVIRONMENTAL HEALTH, 535 WEST  
701. DO NOT DETACH GEOLOGICAL/WATER  
SHEET PROPER WELL LOCATION.

# GEOLOGICAL AND WATER SURVEYS WELL RECORD

Completed 12-6-74

10. Property owner Orland Cruse Well No. 5377  
Address 5377 S. Bluff St. Decatur, Ill.  
Driller Ed. F. Fickel License No. 92-553  
11. Permit No. 34072 Date Dec. 23  
12. Water from Sand 13. County Winnebago  
at depth 68 to 70 ft. Sec. 6  
14. Screen: Diam. 4 in. Twp. 46N  
Length: 2 ft. Slot 15 Rge. 2E  
Elev.         

## 15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)
4	BLK. P.E. 11#	0	68
4	Johnson 5# green	68	70

SHOW LOCATION IN SECTION PLAT  
100' SL, 100' EL, SE SE NW (permit)

16. Size Hole below casing:          in.  
17. Static level 52 ft. below casing top which is          ft.  
above ground level. Pumping level 53 ft. when pumping at 100 gpm for 4 hours. Sub. pump

18. FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
<u>Sand &amp; gravel</u>	<u>30</u>	<u>30</u>
<u>Sand</u>	<u>10</u>	<u>70</u>

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Ed. Fickel DATE Dec. 30

COUNTY NO. 23416

WINNEBAGO

6-46N-2E

GEOLOGICAL AND WATER SURVEYS WELL RECORD

Completed 4-5-72

10. Property owner Rockton Sewage Dis. Well No. 1

Address Rockton, Ill.

Driller Ed. Thompson License No. 92-588

Permit No. 12211 Date 9-12-72

12. Water from Sandstone 13. County Winnebago

at depth 82 to 122 ft.

14. Screen: Diam. 4 1/4 in.

Length: 15 ft. Slot 1/8

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)	SHOW LOCATION IN SECTION PLAT
6	3 1/2" Steel	0	82	600' NL, 500' WL of SW NW NW (Permit)

16. Size Hole below casing: 6 in.

17. Static level 12 ft. below casing top which is 2 ft. above ground level. Pumping level 40 ft. when pumping at 5 gpm for 8 hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	clay & gravel	20	20
	Sand	10	30
	clay & gravel	48	78
	Sandstone	42	120

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Ed. Thompson DATE April 11-72

COUNTY No. 2316

GEOLOGICAL WATER SURVEYS WATER WELL RECORD

Completed 1-20-69

10. Dept. Mines and Minerals permit No. 6291 Year 1968

11. Property owner Village of Rockton Well No. 5

Address Village Hall, Rockton, Illinois

Driller Milaege Well & Pump License No. 92-267

12. Water from Galesville 13. County Winnebago

at depth 550 to 728 ft.

14. Screen: Diam. 4 1/4 in.

Length: 15 ft. Slot 1/8

15. Casing and Liner Pipe

Diam. (in.)	Kind and Weight	From (ft.)	To (ft.)	SHOW LOCATION IN SECTION PLAT
20	Steel - 78#	0	45	21' SL, 240' WL of SW (permit)
16	Steel - 65#	0	200	

16. Size Hole below casing: 15-1 1/4 in.

17. Static level 100 ft. below casing top which is 2 ft. above ground level. Pumping level 195 ft. when pumping at 934 gpm for 24 hours.

18.	FORMATIONS PASSED THROUGH	THICKNESS	DEPTH OF BOTTOM
	Glacial Drift	45	45
	Galena Platteville Dolomite	105	150
	St. Peter Sandstone	165	315
	Franconian Dolomite	235	550
	Galesville Sandstone	178	728

(CONTINUE ON SEPARATE SHEET IF NECESSARY)

SIGNED Milaege Well & Pump Co. Inc. DATE Mar. 25, 1969


COUNTY No. 1856

## ILLINOIS GEOLOGICAL SURVEY, URBANA

Series	Thickness	Top	Bottom
coarse sand and gravel		0	1
fine sand		1	20
coarse sand and gravel		20	42
limestone		42	120
		120	---
meter, length and type of material left in well:			
40' of shutter screen made of bronze. #5 openings.			
80' of 16" inside casing made of 3/8" steel with welded connections.			
20' of 42" outside casing made of 1/16 Steel with welded connections.			
20 yards of gravel used in well. Size: buckshot.			
test of well. Did you use test or permanent pump? test. Size of bowl: 12" SSKIC			
water used: E: horse power: 110.			
size of orifice: 10" X 8"			
mining test - measurements from ground level:			
me G.P.M. Static Drawdown Pumping Level			
hr. 1500 43 24 67'			
test			
covery in 5 minutes: full.			
do you seal bottom of well? yes Thickness: 1/2"			
Material: steel plate.			
is well under-reamed? no			
is screen was placed at bottom.			
depth of well (from ground level to top of plug):			
120'			
is cement placed around or between any of the casings? yes - ready mix from ground level to bottom of well (from ground level to top of plug).			

Mr. Layne-Western Company  
 City of Rockton  
 July 1956  
 County No. 139  
 Layne-Western Company

NE of town; SE 1/4 of section  
 WINNEBAGO  
 13-46N-1E




## ILLINOIS GEOLOGICAL SURVEY, URBANA

Series	Thickness	Top	Bottom
Summary Sample Study by G. H. Emrich 5/57			
Pleistocene series			
Soil, sandy	2		2
Gravel, very coarse; sand, trace silt, grayish-brown, very coarse to coarse, little medium, calcareous	18		20
Sand, slightly gravelly, trace silt, brown, very coarse to coarse, little medium, calcareous	22		42
Gravel, very coarse; sand, grayish-brown, very coarse to medium, little fine, calcareous, clean	23		65
Sand, grayish-buff, fine to coarse, calcareous, clean	5		70
Gravel, very coarse; sand, grayish-brown, fine to very coarse, calcareous, clean	15		85
Gravel, very coarse; little sand, as above	5		90
Gravel, very coarse; sand, as above	25		115
Gravel, very coarse, calcareous, clean	5		120
"Limestone"			120
			TD

← This well currently identified as Rockton #5 by IL EPA/D.P.W.'s see Ref #17  
 Pages 875-876

COMPANY Layne-Western Company  
 FARM City of Rockton  
 DATE DRILLED 1956  
 AUTHORITY G. H. Emrich  
 LOCATION NE SE  
 COUNTY WINNEBAGO  
 NO. 1-56  
 COUNTY NO. 139  
 S.S. #27475  
 13-46N-1E



APPENDIX F  
IEPA SITE PHOTOGRAPHS

# Photo Location Map

SCALE 1" = 50'

UPON THE LOT 65, COUNTY CLERK'S PLAT OF DISTRICT OF SOUTH BLOOMINGTON, BOOK 15 OF PLATS, PAGE 97 IN

SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)

CHARLES AVENUE

AVENUE

HAYES

AVENUE

DOLE DRIVE

ELMWOOD

SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)

SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)

SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)

SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)

SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)

SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)

SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)

PREMISES CONVEYED BY HARRY E. HAYES TO MARY A. SCANDRETT, LILLIAN J. CUMMINGS AND GEORGE J. HAYES, AS TRUSTEES OF THE ESTATE OF THE LATE HARRY E. HAYES, BY DEED DATED 10/10/1910, RECORDED IN THE OFFICE OF THE COUNTY CLERK OF THE COUNTY OF WINNEBAGO, ILLINOIS, BOOK 15 OF PLATS, PAGE 97 IN

AREA  
1.250 ACRES NET  
1.250 ACRES TOTAL

NOTE: 1" DESIGNATES ABOUT 1" FROM DN  
2" DESIGNATES ABOUT 1/4" FROM DN  
3" DESIGNATES ABOUT 1/2" FROM DN  
4" DESIGNATES ABOUT 3/4" FROM DN  
5" DESIGNATES ABOUT 1" FROM DN

RAILROAD  
C. M. ST. PAUL & N. PACIFIC  
SOUTHERLY LINE OF CHARLES AVENUE (PRODUCED NORTHWESTERLY)



DATE: Nov. 5, 1991

TIME: 1:20 PM

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTOGRAPH NUMBER: 1

LOCATION: W of Hayes Ave.,

between Charles Ave. and

Elmwood Ave. in South

Beloit, IL, (X103).

PICTURE TAKEN TOWARD: NW

COMMENTS: The location is

60' NW of NATC bldg. in

the asphalt behind

Trenwyth Industries

DATE: Nov. 5, 1991

TIME: 2:45 PM

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTOGRAPH NUMBER: 2

LOCATION: W of Hayes Ave.,

between Charles Ave. and

Elmwood Ave. in South

Beloit, IL, (X104).

PICTURE TAKEN TOWARD: N

COMMENTS: The location is

35' W and 37' N of the

new dock at NATC.





DATE: Nov. 5, 1991

TIME: 3:45 PM

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTOGRAPH NUMBER: 3

LOCATION: W of Hayes Ave.,

between Charles Ave. and

Elmwood Ave. in South

Beloit, IL, (X102).

PICTURE TAKEN TOWARD: S

COMMENTS: The location is

40' N of the NE corner of

the truck loading dock at

NATC.

DATE: Nov. 5, 1991

TIME: 4:30 PM

PHOTOGRAPH TAKEN BY:

Timothy J. Murphy

PHOTOGRAPH NUMBER: 4

LOCATION: W of Hayes Ave.,

between Charles Ave. and

Elmwood Ave. in South

Beloit, IL, (X101).

PICTURE TAKEN TOWARD: E-SE

COMMENTS: The location is

40.5' W of NATC dock in

the center of the ditch.





DATE: Nov. 5, 1991

TIME: 4:50 PM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 5

LOCATION: W of Hayes Ave.,

between Charles Ave. and

Elmwood Ave. in South

Beloit, IL, (X105).

PICTURE TAKEN TOWARD: E

COMMENTS: The location is

90' W of where the asphalt

ends in a low spot.

DATE: Nov. 5, 1991

TIME: 5:15 PM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 6

LOCATION: W of Hayes Ave.,

between Charles Ave. and

Elmwood Ave. in South

Beloit, IL, (X106).

PICTURE TAKEN TOWARD: E

COMMENTS: The location is

47' from the E end of the

stockpiled soil W of NATC.





DATE: Nov. 5, 1991

TIME: 5:45 PM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 7

LOCATION: St. Peters School

on Elmwood Ave. in

Beloit, IL, (X107).


PICTURE TAKEN TOWARD: NW

COMMENTS: The location is

22' S of Elmwood Ave. and

39' E of the sidewalk

on the school's W side.



DATE: Nov. 6, 1991

TIME: 9:25 AM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 8

LOCATION: On Hayes Ave.

in South Beloit, IL,

(G205).

PICTURE TAKEN TOWARD: S

COMMENTS: This is the

Klinkhammer residence at

528 Hayes Ave.





DATE: Nov. 6, 1991

TIME: 10:00 AM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 9

LOCATION: On Hayes Ave.

in South Beloit, IL,

(G206).

PICTURE TAKEN TOWARD: E

COMMENTS: This is the

Perry residence at

530 Hayes Ave.



DATE: Nov. 6, 1991

TIME: 10:40 AM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 10

LOCATION: On Hayes Ave.

in South Beloit, IL,

(G208).

PICTURE TAKEN TOWARD: SW

COMMENTS: This is the

Willie residence at

521 Hayes Ave.





DATE: Nov. 6, 1991

TIME: 11:15 AM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 11

LOCATION: On Hayes Ave.

in South Beloit, IL,


(G204).

PICTURE TAKEN TOWARD: N

COMMENTS: This is the

Nieves residence at

526 Hayes Ave.



DATE: Nov. 6, 1991

TIME: 11:50 AM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 12

LOCATION: On Hayes Ave.

in South Beloit, IL,

(G202).

PICTURE TAKEN TOWARD: N

COMMENTS: This is the

Schmidt residence at

522 Hayes Ave.





DATE: Nov. 6, 1991

TIME: 12:20 PM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 13

LOCATION: On Hayes Ave.

in South Beloit, IL,


(G201).

PICTURE TAKEN TOWARD: S

COMMENTS: This is the

Pearson residence at

508 Hayes Ave.



DATE: Nov. 6, 1991

TIME: 12:55 PM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 14

LOCATION: On Hayes Ave.

in South Beloit, IL,


(G203).

PICTURE TAKEN TOWARD: NW

COMMENTS: This is a 5

family dwelling at

524 Hayes Ave.





DATE: Nov. 6, 1991

TIME: 1:30 PM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 15

LOCATION: On Hayes Ave.

in South Beloit, IL,


(G209).

PICTURE TAKEN TOWARD: S

COMMENTS: This is the

McMahon residence at

528 Hayes Ave.



DATE: Nov. 6, 1991

TIME: 2:35 PM

PHOTOGRAPH TAKEN BY: \_\_\_\_\_

Timothy J. Murphy

PHOTOGRAPH NUMBER: 16

LOCATION: On Hayes Ave.

in South Beloit, IL,

(G207).

PICTURE TAKEN TOWARD: SE

COMMENTS: This is the

Baden residence at

527 Hayes Ave.





**APPENDIX G**

**1987 RAPPS REPORT**

**CONTAINS MONITOR WELL LOGS AND GROUNDWATER FLOW MAPS**

ENVIRONMENTAL ENGINEERING

September 17, 1987

Illinois Environmental Protection Agency  
Enforcement Section  
2200 Churchill Road  
P.O. Box 19276  
Springfield, Illinois 62794-9276

ATTN: Steve Strauss

1  
(217) 782-5544

RE: S. Beloit/Magnetic Data  
Carriers - Hanson Equipment Co.  
I.D. No.: 2010455012

Dear Steve:

In follow-up to our September 2, 1987 meeting regarding the above site, enclosed are the following.

1. An excerpt from the USGS South Beloit Quadrangle Topographic Map showing the location of the former Hanson Equipment Company property.
2. A site map of the property indicating the names of the present occupants of the buildings. The locations of the recently installed monitoring wells are also shown.
3. Information regarding the installation of the four monitoring wells.
4. Monitoring well data summary for the sampling which occurred on June 15, 1987.
5. Piezometric surface map indicating the direction of groundwater flow at the time of the June 15, 1987 sampling.
6. Contour plots of the concentrations of selected parameters from the analysis results for the June 15, 1987 sampling.


Steve Strauss  
September 17, 1987  
Page 2

7. Complete analysis results for the June 15, 1987 sampling.

Since our meeting, we have been able to confirm the existence of a waterwell located on property northwest of the subject site. This property is presently owned by Trendwith Industries. The well is located inside the facility building (See Site Diagram). According to Trendwith, the well is presently in use and supplies water for employee sanitary facilities. The well is 1.5 inches in diameter and 15 feet deep. Trendwith pumps about 400 gallons of water per day from the well. Trendwith indicated that the well is contaminated with chlorinated organics and that they filter the water with an activated carbon unit. They have an analysis of the unfilter water and they indicated that they would send such to me shortly.

Should you have any questions on the enclosed information, please call.


Sincerely,


A handwritten signature in cursive script that reads "Daniel V. Flynn".

Daniel V. Flynn  
M. RAPPS ASSOCIATES, INC.

DVF/jh

cc: Steve Balsley  
Bob Carson  
Bob Wengrow







**Professional Service Industries, Inc.**  
A & H/Flood Engineering Division

June 5, 1987

DeBruyne, Yalden & Olsen  
838 North Main Street  
Rockford, Illinois 61103

Attention: Mr. Joseph Olsen

Re: Monitor Well Installation  
Hanson Products  
South Beloit, Illinois  
PSI File No.: 152-75073

Gentlemen:

Presented herein are the boring logs and monitor well installation diagrams for work performed at the above referenced project. It has been a pleasure to have been of service to you on this project. If you have any questions, please call.

Very truly yours,

**A&H/FLOOD ENGINEERING DIVISION**

A handwritten signature in black ink, appearing to read "Gregory R. Reuter", is written over the typed name.

Gregory R. Reuter  
Branch Manager

A large, stylized handwritten signature in black ink, appearing to read "Thomas S. LeDonne", is written over the typed name.

Thomas S. LeDonne, P.E.  
Illinois 34585  
Vice President

GRR/TSL:sjp

cc: (3) M. Rapps Associates, Inc.  
(1) Barrick, Switzer, Long,  
Balsley & Van Evera

## PROJECT AUTHORIZATION

Authorization to perform this work was as per the signed June 9, 1987 proposal (PSI No. 152-105) from Professional Service Industries, Inc. to DeBruyne, Yalden & Olsen.

## FIELD EXPLORATION

Four soil borings were drilled at the approximate locations as shown on the enclosed Plan of Borings. The borings were drilled with a drilling rig equipped with a rotary head and were advanced using 3 $\frac{1}{4}$  inch I.D. hollow stem auger. As requested, no samples were obtained and the borings were logged based on the auger cuttings.

Borings G101 and G102 were offset to the approximate locations as shown on the enclosed Plan of Borings. The borings were relocated upon instructions by Mr. Roger Taylor of North American Tool.

Prior to drilling, and between borings, the hollow-stem auger and stainless steel well pipe was washed with Alconox®, which is a non-forming detergent, rinsed and steam cleaned. Water used during this cleaning operation was supplied on-site by the client.

## SUBSURFACE CONDITIONS

The materials encountered during the boring operations have been visually classified and are described in detail on the enclosed boring logs.

The stratification of the soils, as shown on the boring logs, represents the soil conditions in the actual boring locations, and other variations may occur between the borings. Lines of demarcation represent the approximate boundary between the soil types, but the transition may be gradual.

It is to be noted that, whereas the borings are drilled and sampled by experienced drillers, it is sometimes difficult to record changes in stratification within narrow limits.

Generally black organic silt was encountered from the ground surface in all borings to depths ranging from approximately four (4) to six (6) feet below grade. An approximate two-foot thick stratum of gray sandy silt was also encountered underlying the black organic silt in boring G104.

Next, a stratum of tan clayey coarse sand and fine to coarse gravel was encountered the boring completion depths of twenty (20) feet below existing grade. During the boring operations, this clayey sand and gravel had entered the hollow stem auger and prior to installation of the monitor wells, this clayey sand and gravel was removed using wash boring techniques.

Groundwater was measured in borings G101, G103 and G104 at depths of six (6) to seven (7) feet below grade while drilling. Even though no water was measured in boring G102 upon completion of drilling, efforts to bail the water introduced into the boring during the wash boring operation proved useless since water kept entering the auger from the surrounding soils.

#### MONITOR WELL INSTALLATION

Upon completion of drilling, monitor wells were installed in each of the four borings. A monitor well installation diagram for each well is presented on the corresponding boring logs. All monitor wells were constructed as instructed by M. Rapps Associates, Inc.


Each well consisted of two-inch diameter, stainless steel 316 pipe. A ten-foot section of #10 slotted stainless steel 316 screen was attached to the bottom of each well. Silica sand was used as a sand pack around the well




screen. A two-foot thick bentonite pellet seal was constructed above the sand pack and the remaining bore hole annulus was grouted to the surface with cement/bentonite grout. A concrete pad, protective wall cover, and key alike locks were installed at the surface. Three sets of keys were retained by Mr. Roger Taylor at North American Tool and one set was retained by PSI.

All wells were developed upon completion using a Teflon® bailer. The wells were bailed until clean water was observed.

Professional Service Industries



NOT TO SCALE



PROJECT NAME

Monitor Well Installation  
Hanson Products  
South Beloit, Illinois

PLAN OF BORINGS

PROJECT NO.

152-75073

DATE

June 3-4, 1987

# Professional Service Industries, Inc.

## RECORD OF SUBSURFACE EXPLORATION

Boring G101

Project Name: Monitor Well Installation  
Hanson Products

Date of Boring: June 4, 1987

Site: South Beloit, Illinois

Project No.: 152-75073

DESCRIPTION	DEPTH	SAMPLE	N	% REC.	MONITOR WELL INSTALLATION
<u>SURFACE</u>					
Black organic SILT, with occasional sand					+2.6' Locking Well Protector
					Stainless Steel Cap
Tan clayey coarse SAND and fine to coarse GRAVEL	10'				Concrete Pad
					Cement - bentonite grout
	20'				
Total depth of boring = 20'					
Water measured at 6' in boring while drilling					2" Dia. Stainless Steel 316 Pipe
					-6' Bentonite Pellet Seal
					-8'
					-10' #10 Stainless Steel Screen
					Clean quartz sand
					-20' Stainless steel end cap

# Professional Service Industries, Inc.

## RECORD OF SUBSURFACE EXPLORATION

Boring G102

Project Name: Monitor Well Installation  
Hanson Products Date of Boring: June 4, 1987  
South Beloit, Illinois Project No.: 152-75073  
 Site: \_\_\_\_\_


DESCRIPTION	DEPTH	SAMPLE	N	% REC.	MONITOR WELL INSTALLATION
<u>SURFACE</u> Black organic SILT, with occasional fine gravel					+2.1' Locking Well Protector Stainless Steel Cap
Tan clayey coarse SAND and fine to coarse GRAVEL, wet	10'				Concrete Pad Cement - bentonite grout
Total depth of boring = 20'	20'				2" Dia. Stainless Steel 316 Pipe Bentonite Pellet Seal #10 Stainless Steel Screen Clean quartz sand Stainless steel end cap

# Professional Service Industries, Inc.

## RECORD OF SUBSURFACE EXPLORATION

Boring G103

Project Name: Monitor Well Installation  
Hanson Products Date of Boring: June 3, 1987  
South Beloit, Illinois Project No.: 152-75073  
 Site: \_\_\_\_\_



# Professional Service Industries, Inc.


## RECORD OF SUBSURFACE EXPLORATION

Boring G104

Monitor Well Installation  
Hanson Products

Project Name: \_\_\_\_\_ Date of Boring: June 3, 1987

Site: South Beloit, Illinois Project No.: 152-75073




# HANSON PRODUCTS

## MONITORING WELL DATA SUMMARY

( 6-15-87 )

Well Number	Top of Pipe	Ground Surface	Water Elevation
G101	742.36	739.34	735.89
G102	742.89	740.25	736.04
G103	741.72	738.30	735.82
G104	740.21	738.43	735.66




HANSON EQUIPMENT

# PIEZOMETRIC SURFACE


Scale: 1" = 100' | Date: (6/15/87)

M. RAPPS ASSOCIATES, INC.






HANSON EQUIPMENT
Tetrachloroethylene (PPb)
Scale: 1"=100'




HANSON EQUIPMENT

Total Organic Halogens  
(PPb)


Scale: 1"=100'




HANSON EQUIPMENT	
Total Dissolved Solids (PPb)	
Scale: 1"=100'	



HANSON EQUIPMENT
C-1,2- Dichloroethylene (PPb)
Scale: 1"=100'




HANSON EQUIPMENT
1,1- Dichloroethane (PPb)
Scale: 1"=100'




HANSON EQUIPMENT

1,1,1- Trichloroethane  
(ppb)

Scale: 1"=100'




HANSON EQUIPMENT
Trichloroethylene (PPb)
Scale: 1"=100'



HANSON EQUIPMENT
1,1- Dichloroethylene (PPb)
Scale: 1"=100'





HANSON EQUIPMENT
1,1- Dichloroethane (PPb)
Scale: 1"=100'



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47360

SAMPLE DESCRIPTION: G101


Hanson Products, South Beloit, IL

Date Taken: 06-15-87 1640

Date Received: 06-16-87 1030

Chloride	96.	mg/L
Solids, Dissolved	352.	mg/L
Sulfate	30.	mg/L
Total Organic Carbon (TOC)	63.2	mg/L
Total Organic Halogens	0.028	mg/L
Arsenic	<0.001	mg/L
Barium	0.02	mg/L
Cadmium	0.004	mg/L
Chromium, Total	0.009	mg/L
Lead	<0.01	mg/L
Mercury	<0.0001	mg/L
Selenium	<0.001	mg/L
Silver	0.001	mg/L

All inorganic results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47360

SAMPLE DESCRIPTION: G101

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1640

Date Received: 06-16-87 103

### VOLATILE COMPOUNDS

Acrolein	<10.	ug/L
Acrylonitrile	<10.	ug/L
Benzene	<1.0	ug/L
Bromodichloromethane	<1.0	ug/L
Bromoform	<1.0	ug/L
Bromomethane	<10.	ug/L
Carbon tetrachloride	<1.0	ug/L
Chlorobenzene	<1.0	ug/L
Chloroethane	<10.	ug/L
2-Chloroethyl vinyl ether	<1.0	ug/L
Chloroform	<1.0	ug/L
Chloromethane	<10.	ug/L
Dibromochloromethane	<1.0	ug/L
1,2-Dichlorobenzene	<1.0	ug/L
1,3-Dichlorobenzene	<1.0	ug/L
1,4-Dichlorobenzene	<1.0	ug/L
1,1-Dichloroethane	9.8	ug/L
1,2-Dichloroethane	<1.0	ug/L
1,1-Dichloroethene	12.5	ug/L
trans-1,2-Dichloroethene	<1.0	ug/L
cis-1,2-Dichloroethene	1.5	ug/L
1,2-Dichloropropane	<1.0	ug/L
cis-1,3-Dichloropropene	<1.0	ug/L
trans-1,3-Dichloropropene	<1.0	ug/L
Ethylbenzene	<1.0	ug/L

All inorganic results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgpoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47360

SAMPLE DESCRIPTION: G101

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1640

Date Received: 06-16-87 103

### VOLATILE COMPOUNDS

Methyl ethyl ketone	<1.0	ug/L
Methylene chloride	<5.0	ug/L
1,1,2,2-Tetrachloroethane	<1.0	ug/L
Tetrachloroethene	5.8	ug/L
Toluene	<1.0	ug/L
1,1,1-Trichloroethane	127.	ug/L
1,1,2-Trichloroethane	<1.0	ug/L
Trichloroethene	3.1	ug/L
Vinyl chloride	<10.	ug/L
Xylenes	<1.0	ug/L

All inorganic results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

Austin Division

2621-130 Ridgpoint Dr.  
Austin TX 78754  
512-428-8905

Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312 299 2100

Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312 555 4450

Rockford Division

3548 35th St.  
Rockford IL 61109  
815 398 1100

Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47360

SAMPLE DESCRIPTION: G101

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1640

Date Received: 06-16-87 1030

### BASE/NEUTRAL COMPOUNDS

Acenaphthene	<10.	ug/L
Acenaphthylene	<10.	ug/L
Anthracene	<10.	ug/L
Benzidine	<50.	ug/L
Benzo(a)anthracene	<10.	ug/L
Benzo(b)fluoranthene	<10.	ug/L
Benzo(k)fluoranthene	<10.	ug/L
Benzo(a)pyrene	<10.	ug/L
Benzo(ghi)perylene	<10.	ug/L
Benzyl butyl phthalate	<10.	ug/L
Bis(2-chloroethyl)ether	<10.	ug/L
Bis(2-chloroethoxy)methane	<10.	ug/L
Bis(2-ethylhexyl)phthalate	<10.	ug/L
Bis(2chloroisopropyl)ether	<10.	ug/L
4-Bromophenyl phenyl ether	<10.	ug/L
2-Chloronaphthalene	<10.	ug/L
4-Chlorophenylphenyl ether	<10.	ug/L
Chrysene	<10.	ug/L
Dibenzo(a,h)anthracene	<10.	ug/L
Di-n-butylphthalate	<10.	ug/L
1,3-Dichlorobenzene	<10.	ug/L
1,2-Dichlorobenzene	<10.	ug/L
1,4-Dichlorobenzene	<10.	ug/L
3,3-Dichlorobenzidine	<20.	ug/L
Diethyl phthalate	<10.	ug/L

All inorganic results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2021-130 Ridgpoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-9171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47360

SAMPLE DESCRIPTION: G101

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1640

Date Received: 06-16-87 103

### BASE/NEUTRAL COMPOUNDS

Dimethyl phthalate	<10.	ug/L
2,4-Dinitrotoluene	<10.	ug/L
2,6-Dinitrotoluene	<10.	ug/L
Di-n-octylphthalate	<10.	ug/L
Fluoranthene	<10.	ug/L
Fluorene	<10.	ug/L
Hexachlorobenzene	<10.	ug/L
Hexachlorobutadiene	<10.	ug/L
Hexachlorocyclopentadiene	<25.	ug/L
Hexachloroethane	<10.	ug/L
Indeno(1,2,3-cd)pyrene	<10.	ug/L
Isophorone	<10.	ug/L
Naphthalene	<10.	ug/L
Nitrobenzene	<10.	ug/L
N-Nitrosodimethylamine	<10.	ug/L
N-Nitrosodiphenylamine	<10.	ug/L
N-Nitrosodi-n-propylamine	<10.	ug/L
Phenanthrene	<10.	ug/L
Pyrene	<10.	ug/L
1,2,4-Trichlorobenzene	<10.	ug/L

All inorganic results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgpoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-374-0171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47360

SAMPLE DESCRIPTION: G101

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1640

Date Received: 06-16-87 10

### ACID COMPOUNDS

4-Chloro-3-methylphenol	<10.	ug/L
2-chlorophenol	<10.	ug/L
2,4-Dichlorophenol	<10.	ug/L
2,4-Dimethylphenol	<10.	ug/L
2,4-Dinitrophenol	<50.	ug/L
2-Methyl-4,6-dinitrophenol	<50.	ug/L
2-Nitrophenol	<10.	ug/L
4-Nitrophenol	<50.	ug/L
Pentachlorophenol	<50.	ug/L
Phenol	<10.	ug/L
2,4,6-Trichlorophenol	<10.	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-974-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47361

SAMPLE DESCRIPTION: G102


Hanson Products, South Beloit, IL

Date Taken: 06-15-87 1705

Date Received: 06-16-87 103

Chloride	112.	mg/L
Solids, Dissolved	480.	mg/L
Sulfate	38.	mg/L
Total Organic Carbon (TOC)	67.8	mg/L
Total Organic Halogens	<0.02	mg/L
Arsenic	<0.001	mg/L
Barium	0.03	mg/L
Cadmium	0.004	mg/L
Chromium, Total	0.011	mg/L
Lead	<0.01	mg/L
Mercury	<0.0001	mg/L
Selenium	<0.001	mg/L
Silver	0.001	mg/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

Austin Division

Bartlett Division

Rosner/Runyon Division

Rockford Division

Corporate Office

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

3548 35th St.  
Rockford IL 61109  
815-374-2171

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100





## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47361

SAMPLE DESCRIPTION: G102

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1705

Date Received: 06-16-87 103

### VOLATILE COMPOUNDS

Acrolein	<10.	ug/L
Acrylonitrile	<10.	ug/L
Benzene	<1.0	ug/L
Bromodichloromethane	<1.0	ug/L
Bromoform	<1.0	ug/L
Bromomethane	<10.	ug/L
Carbon tetrachloride	<1.0	ug/L
Chlorobenzene	<1.0	ug/L
Chloroethane	<10.	ug/L
2-Chloroethyl vinyl ether	<1.0	ug/L
Chloroform	<1.0	ug/L
Chloromethane	<10.	ug/L
Dibromochloromethane	<1.0	ug/L
1,2-Dichlorobenzene	<1.0	ug/L
1,3-Dichlorobenzene	<1.0	ug/L
1,4-Dichlorobenzene	<1.0	ug/L
1,1-Dichloroethane	<1.0	ug/L
1,2-Dichloroethane	<1.0	ug/L
1,1-Dichloroethene	<1.0	ug/L
trans-1,2-Dichloroethene	<1.0	ug/L
cis-1,2-Dichloroethene	<1.0	ug/L
1,2-Dichloropropane	<1.0	ug/L
cis-1,3-Dichloropropene	<1.0	ug/L
trans-1,3-Dichloropropene	<1.0	ug/L
Ethylbenzene	<1.0	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgpoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-374-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47361

SAMPLE DESCRIPTION: G102

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1705

Date Received: 06-16-87 103

### VOLATILE COMPOUNDS

Methyl ethyl ketone	<1.0	ug/L
Methylene chloride	<5.0	ug/L
1,1,2,2-Tetrachloroethane	<1.0	ug/L
Tetrachloroethene	<1.0	ug/L
Toluene	<1.0	ug/L
1,1,1-Trichloroethane	<1.0	ug/L
1,1,2-Trichloroethane	<1.0	ug/L
Trichloroethene	<1.0	ug/L
Vinyl chloride	<10.	ug/L
Xylenes	<1.0	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47361

SAMPLE DESCRIPTION: G102

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1705

Date Received: 06-16-87 10

### BASE/NEUTRAL COMPOUNDS

Acenaphthene	<10.	ug/L
Acenaphthylene	<10.	ug/L
Anthracene	<10.	ug/L
Benzidine	<50.	ug/L
Benzo(a)anthracene	<10.	ug/L
Benzo(b)fluoranthene	<10.	ug/L
Benzo(k)fluoranthene	<10.	ug/L
Benzo(a)pyrene	<10.	ug/L
Benzo(ghi)perylene	<10.	ug/L
Benzyl butyl phthalate	<10.	ug/L
Bis(2-chloroethyl)ether	<10.	ug/L
Bis(2-chloroethoxy)methane	<10.	ug/L
Bis(2-ethylhexyl)phthalate	<10.	ug/L
Bis(2chloroisopropyl)ether	<10.	ug/L
4-Bromophenyl phenyl ether	<10.	ug/L
2-Chloronaphthalene	<10.	ug/L
4-Chlorophenylphenyl ether	<10.	ug/L
Chrysene	<10.	ug/L
Dibenzo(a,h)anthracene	<10.	ug/L
Di-n-butylphthalate	<10.	ug/L
1,3-Dichlorobenzene	<10.	ug/L
1,2-Dichlorobenzene	<10.	ug/L
1,4-Dichlorobenzene	<10.	ug/L
3,3-Dichlorobenzidine	<20.	ug/L
Diethyl phthalate	<10.	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815 871 2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312 289 3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47361

SAMPLE DESCRIPTION: G102

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1705

Date Received: 06-16-87 103

### BASE/NEUTRAL COMPOUNDS

Dimethyl phthalate	<10.	ug/L
2,4-Dinitrotoluene	<10.	ug/L
2,6-Dinitrotoluene	<10.	ug/L
Di-n-octylphthalate	<10.	ug/L
Fluoranthene	<10.	ug/L
Fluorene	<10.	ug/L
Hexachlorobenzene	<10.	ug/L
Hexachlorobutadiene	<10.	ug/L
Hexachlorocyclopentadiene	<25.	ug/L
Hexachloroethane	<10.	ug/L
Indeno(1,2,3-cd)pyrene	<10.	ug/L
Isophorone	<10.	ug/L
Naphthalene	<10.	ug/L
Nitrobenzene	<10.	ug/L
N-Nitrosodimethylamine	<10.	ug/L
N-Nitrosodiphenylamine	<10.	ug/L
N-Nitrosodi-n-propylamine	<10.	ug/L
Phenanthrene	<10.	ug/L
Pyrene	<10.	ug/L
1,2,4-Trichlorobenzene	<10.	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47361

SAMPLE DESCRIPTION: G102

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1705

Date Received: 06-16-87 1030

### ACID COMPOUNDS

4-Chloro-3-methylphenol	<10.	ug/L
2-chlorophenol	<10.	ug/L
2,4-Dichlorophenol	<10.	ug/L
2,4-Dimethylphenol	<10.	ug/L
2,4-Dinitrophenol	<50.	ug/L
2-Methyl-4,6-dinitrophenol	<50.	ug/L
2-Nitrophenol	<10.	ug/L
4-Nitrophenol	<50.	ug/L
Pentachlorophenol	<50.	ug/L
Phenol	<10.	ug/L
2,4,6-Trichlorophenol	<10.	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47362

SAMPLE DESCRIPTION: G103


Hanson Products, South Beloit, IL

Date Taken: 06-16-87 0930

Date Received: 06-16-87 10

Chloride	82.	mg/L
Solids, Dissolved	428.	mg/L
Sulfate	26.	mg/L
Total Organic Carbon (TOC)	61.6	mg/L
Total Organic Halogens	<0.02	mg/L
Arsenic	<0.001	mg/L
Barium	<0.01	mg/L
Cadmium	0.002	mg/L
Chromium, Total	0.005	mg/L
Lead	0.01	mg/L
Mercury	<0.0001	mg/L
Selenium	<0.001	mg/L
Silver	0.001	mg/L

Note: Metals results on filtered sample.

  
Toni Bartner, Manager  
Rockford Division

### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47362

SAMPLE DESCRIPTION: G103

Hanson Products, South Beloit, IL


Date Taken: 06-16-87 0930

Date Received: 06-16-87 103

### VOLATILE COMPOUNDS

Acrolein	<10.	ug/L
Acrylonitrile	<10.	ug/L
Benzene	<1.0	ug/L
Bromodichloromethane	<1.0	ug/L
Bromoform	<1.0	ug/L
Bromomethane	<10.	ug/L
Carbon tetrachloride	<1.0	ug/L
Chlorobenzene	<1.0	ug/L
Chloroethane	<10.	ug/L
2-Chloroethyl vinyl ether	<1.0	ug/L
Chloroform	<1.0	ug/L
Chloromethane	<10.	ug/L
Dibromochloromethane	<1.0	ug/L
1,2-Dichlorobenzene	<1.0	ug/L
1,3-Dichlorobenzene	<1.0	ug/L
1,4-Dichlorobenzene	<1.0	ug/L
1,1-Dichloroethane	<1.0	ug/L
1,2-Dichloroethane	<1.0	ug/L
1,1-Dichloroethene	<1.0	ug/L
trans-1,2-Dichloroethene	<1.0	ug/L
cis-1,2-Dichloroethene	<1.0	ug/L
1,2-Dichloropropane	<1.0	ug/L
cis-1,3-Dichloropropene	<1.0	ug/L
trans-1,3-Dichloropropene	<1.0	ug/L
Ethylbenzene	<1.0	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47362

SAMPLE DESCRIPTION: G103

Hanson Products, South Beloit, IL


Date Taken: 06-16-87 0930

Date Received: 06-16-87 103

### BASE/NEUTRAL COMPOUNDS

Acenaphthene	<10.	ug/L
Acenaphthylene	<10.	ug/L
Anthracene	<10.	ug/L
Benzidine	<50.	ug/L
Benzo(a)anthracene	<10.	ug/L
Benzo(b)fluoranthene	<10.	ug/L
Benzo(k)fluoranthene	<10.	ug/L
Benzo(a)pyrene	<10.	ug/L
Benzo(ghi)perylene	<10.	ug/L
Benzyl butyl phthalate	<10.	ug/L
Bis(2-chloroethyl)ether	<10.	ug/L
Bis(2-chloroethoxy)methane	<10.	ug/L
Bis(2-ethylhexyl)phthalate	<10.	ug/L
Bis(2chloroisopropyl)ether	<10.	ug/L
4-Bromophenyl phenyl ether	<10.	ug/L
2-Chloronaphthalene	<10.	ug/L
4-Chlorophenylphenyl ether	<10.	ug/L
Chrysene	<10.	ug/L
Dibenzo(a,h)anthracene	<10.	ug/L
Di-n-butylphthalate	<10.	ug/L
1,3-Dichlorobenzene	<10.	ug/L
1,2-Dichlorobenzene	<10.	ug/L
1,4-Dichlorobenzene	<10.	ug/L
3,3-Dichlorobenzidine	<20.	ug/L
Diethyl phthalate	<10.	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgpoint Dr.  
Austin TX 78754  
512-928-8906

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-555-4460

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-391-1071

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103





## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47362

SAMPLE DESCRIPTION: G103

Hanson Products, South Beloit, IL


Date Taken: 06-16-87 0930

Date Received: 06-16-87 10

### VOLATILE COMPOUNDS

Methyl ethyl ketone	<1.0	ug/L
Methylene chloride	<5.0	ug/L
1,1,2,2-Tetrachloroethane	<1.0	ug/L
Tetrachloroethene	<1.0	ug/L
Toluene	<1.0	ug/L
1,1,1-Trichloroethane	<1.0	ug/L
1,1,2-Trichloroethane	<1.0	ug/L
Trichloroethene	<1.0	ug/L
Vinyl chloride	<10.	ug/L
Xylenes	<1.0	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47362

SAMPLE DESCRIPTION: G103

Hanson Products, South Beloit, IL


Date Taken: 06-16-87 0930

Date Received: 06-16-87 103

### BASE/NEUTRAL COMPOUNDS

Dimethyl phthalate	<10.	ug/L
2,4-Dinitrotoluene	<10.	ug/L
2,6-Dinitrotoluene	<10.	ug/L
Di-n-octylphthalate	<10.	ug/L
Fluoranthene	<10.	ug/L
Fluorene	<10.	ug/L
Hexachlorobenzene	<10.	ug/L
Hexachlorobutadiene	<10.	ug/L
Hexachlorocyclopentadiene	<25.	ug/L
Hexachloroethane	<10.	ug/L
Indeno(1,2,3-cd)pyrene	<10.	ug/L
Isophorone	<10.	ug/L
Naphthalene	<10.	ug/L
Nitrobenzene	<10.	ug/L
N-Nitrosodimethylamine	<10.	ug/L
N-Nitrosodiphenylamine	<10.	ug/L
N-Nitrosodi-n-propylamine	<10.	ug/L
Phenanthrene	<10.	ug/L
Pyrene	<10.	ug/L
1,2,4-Trichlorobenzene	<10.	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgpoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47362

SAMPLE DESCRIPTION: G103

Hanson Products, South Beloit, IL

Date Taken: 06-16-87 0930

Date Received: 06-16-87 1030

### ACID COMPOUNDS

4-Chloro-3-methylphenol	<10.	ug/L
2-chlorophenol	<10.	ug/L
2,4-Dichlorophenol	<10.	ug/L
2,4-Dimethylphenol	<10.	ug/L
2,4-Dinitrophenol	<50.	ug/L
2-Methyl-4,6-dinitrophenol	<50.	ug/L
2-Nitrophenol	<10.	ug/L
4-Nitrophenol	<50.	ug/L
Pentachlorophenol	<50.	ug/L
Phenol	<10.	ug/L
2,4,6-Trichlorophenol	<10.	ug/L

Note: Metals results on filtered sample.

Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47363

SAMPLE DESCRIPTION: G104


Hanson Products, South Beloit, IL

Date Taken: 06-15-87 1745

Date Received: 06-16-87 10:00

Chloride	106.	mg/L
Solids, Dissolved	404.	mg/L
Sulfate	21.	mg/L
Total Organic Carbon (TOC)	65.8	mg/L
Total Organic Halogens	0.049	mg/L
Arsenic	<0.001	mg/L
Barium	<0.01	mg/L
Cadmium	<0.001	mg/L
Chromium, Total	<0.001	mg/L
Lead	0.04	mg/L
Mercury	<0.0001	mg/L
Selenium	<0.001	mg/L
Silver	<0.001	mg/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-874-2171

### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100





## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47363

SAMPLE DESCRIPTION: G104

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1745

Date Received: 06-16-87 103

### VOLATILE COMPOUNDS

Acrolein	<10.	ug/L
Acrylonitrile	<10.	ug/L
Benzene	<1.0	ug/L
Bromodichloromethane	<1.0	ug/L
Bromoform	<1.0	ug/L
Bromomethane	<10.	ug/L
Carbon tetrachloride	<1.0	ug/L
Chlorobenzene	<1.0	ug/L
Chloroethane	<10.	ug/L
2-Chloroethyl vinyl ether	<1.0	ug/L
Chloroform	<1.0	ug/L
Chloromethane	<10.	ug/L
Dibromochloromethane	<1.0	ug/L
1,2-Dichlorobenzene	<1.0	ug/L
1,3-Dichlorobenzene	<1.0	ug/L
1,4-Dichlorobenzene	<1.0	ug/L
1,1-Dichloroethane	14.8	ug/L
1,2-Dichloroethane	<1.0	ug/L
1,1-Dichloroethene	15.7	ug/L
trans-1,2-Dichloroethene	<1.0	ug/L
cis-1,2-Dichloroethene	2.2	ug/L
1,2-Dichloropropane	<1.0	ug/L
cis-1,3-Dichloropropene	<1.0	ug/L
trans-1,3-Dichloropropene	<1.0	ug/L
Ethylbenzene	<1.0	ug/L

Note: Metals results on filtered sample.

  
Toni Bartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512 336 8005

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
815 336 8005

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607

#### Rockford Division

3548 35th St.  
Rockford IL 61109

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47363

SAMPLE DESCRIPTION: G104

Hanson Products, South Beloit, IL

Date Taken: 06-15-87 1745

Date Received: 06-16-87 10:00

### VOLATILE COMPOUNDS

Methyl ethyl ketone	<1.0	ug/L
Methylene chloride	<5.0	ug/L
1,1,2,2-Tetrachloroethane	<1.0	ug/L
Tetrachloroethene	4.8	ug/L
Toluene	<1.0	ug/L
1,1,1-Trichloroethane	127.	ug/L
1,1,2-Trichloroethane	<1.0	ug/L
Trichloroethene	3.3	ug/L
Vinyl chloride	<10.	ug/L
Xylenes	<1.0	ug/L

Note: Metals results on filtered sample.

*Toni Gartner*  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgpoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-280-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-1100

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-398-1100

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47363

SAMPLE DESCRIPTION: G104

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1745

Date Received: 06-16-87 103

### BASE/NEUTRAL COMPOUNDS

Acenaphthene	<10.	ug/L
Acenaphthylene	<10.	ug/L
Anthracene	<10.	ug/L
Benzidine	<50.	ug/L
Benzo(a)anthracene	<10.	ug/L
Benzo(b)fluoranthene	<10.	ug/L
Benzo(k)fluoranthene	<10.	ug/L
Benzo(a)pyrene	<10.	ug/L
Benzo(ghi)perylene	<10.	ug/L
Benzyl butyl phthalate	<10.	ug/L
Bis(2-chloroethyl)ether	<10.	ug/L
Bis(2-chloroethoxy)methane	<10.	ug/L
Bis(2-ethylhexyl)phthalate	21.	ug/L
Bis(2chloroisopropyl)ether	<10.	ug/L
4-Bromophenyl phenyl ether	<10.	ug/L
2-Chloronaphthalene	<10.	ug/L
4-Chlorophenylphenyl ether	<10.	ug/L
Chrysene	<10.	ug/L
Dibenzo(a,h)anthracene	<10.	ug/L
Di-n-butylphthalate	<10.	ug/L
1,3-Dichlorobenzene	<10.	ug/L
1,2-Dichlorobenzene	<10.	ug/L
1,4-Dichlorobenzene	<10.	ug/L
3,3-Dichlorobenzidine	<20.	ug/L
Diethyl phthalate	<10.	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

#### Austin Division

2621-130 Ridgepoint Dr.  
Austin TX 78754  
512-928-8905

#### Bartlett Division

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100

#### Rosner/Runyon Division

222 South Morgan St.  
Chicago IL 60607  
312-666-4469

#### Rockford Division

3548 35th St.  
Rockford IL 61109  
815-394-0171

#### Corporate Office

850 West Bartlett Rd.  
Bartlett IL 60103  
312-289-3100



## ANALYTICAL REPORT

Mr. Mike Rogers  
RAPPS ASSOCIATES  
2387 West Monroe  
Springfield, IL 62704

07-01-87

Sample No: 47363

SAMPLE DESCRIPTION: G104

Hanson Products, South Beloit, IL


Date Taken: 06-15-87 1745

Date Received: 06-16-87 103

### BASE/NEUTRAL COMPOUNDS

Dimethyl phthalate	<10.	ug/L
2,4-Dinitrotoluene	<10.	ug/L
2,6-Dinitrotoluene	<10.	ug/L
Di-n-octylphthalate	<10.	ug/L
Fluoranthene	<10.	ug/L
Fluorene	<10.	ug/L
Hexachlorobenzene	<10.	ug/L
Hexachlorobutadiene	<10.	ug/L
Hexachlorocyclopentadiene	<25.	ug/L
Hexachloroethane	<10.	ug/L
Indeno(1,2,3-cd)pyrene	<10.	ug/L
Isophorone	<10.	ug/L
Naphthalene	<10.	ug/L
Nitrobenzene	<10.	ug/L
N-Nitrosodimethylamine	<10.	ug/L
N-Nitrosodiphenylamine	<10.	ug/L
N-Nitrosodi-n-propylamine	<10.	ug/L
Phenanthrene	<10.	ug/L
Pyrene	<10.	ug/L
1,2,4-Trichlorobenzene	<10.	ug/L

Note: Metals results on filtered sample.

  
Toni Gartner, Manager  
Rockford Division

Austin Division

Bartlett Division

Rosner/Runyon Division

Rockford Division

Corporate Office

2621-130 Ridgpoint Dr.  
Austin TX 78754  
512-928-8905

850 West Bartlett Rd.  
Bartlett IL 60103  
312-299-2100

222 South Morgan St.  
Chicago IL 60607  
312-666-1100

3548 35th St.  
Rockford IL 61109  
815-398-1100

850 West Bartlett Rd.  
Bartlett IL 60103  
312-299-2100

APPENDIX H  
1990 WARZYN REPORT



Report  
15275

Site Investigation  
North American Tool Corporation  
South Beloit, Illinois

Prepared for:  
North American Tool Corporation  
South Beloit, Illinois

Prepared by:  
Warzyn Engineering Inc.  
Madison, Wisconsin

November 1990

WARZYN

November 13, 1990

Mr. Roger Taylor  
North American Tool Corporation  
215 Elmwood Avenue  
P.O. Box 116  
South Beloit, Illinois 61080

Re: Site Investigation Report

Dear Mr. Taylor:

Attached is the Site Investigation Report for the North American Tool Corporation (NATCo) property (site) located on Elmwood Avenue in South Beloit, Illinois. The report is provided for your review prior to submittal to the Illinois Environmental Protection Agency (IEPA). The report includes a summary of the work performed and the results of the investigation.

General conclusions of the investigation are as follows:

- Soil contamination appears limited to relatively small areas immediately west and north of the existing building. The majority of contaminated soil in the west area has been excavated and stockpiled on-site.
- Volatile organic compounds (VOCs) in groundwater have been observed in three monitoring wells sampled before the excavation, and beneath the excavation. Proposed Title 35 groundwater level criteria for 1,1-dichloroethene and 1,1,1-trichloroethane have been exceeded in the excavation groundwater sample, but not in the monitoring wells.

Based on the results, we recommend the following additional work to address the remaining concerns at the site:

- Water level data from the site monitoring wells indicate the water table at the site is relatively flat. Groundwater flow direction should be further evaluated by additional measurements. Installation of additional wells should be considered to further define the water table.
- Site monitoring wells should be sampled periodically to monitor for water quality changes or possible groundwater quality criteria exceedances.
- Locations of nearby private water supply wells or municipal wells should be determined, and the potential need for sampling these wells should be assessed.

THE PERFECT BALANCE  
BETWEEN TECHNOLOGY  
AND CREATIVITY

MADISON  
ONE SCIENCE COURT  
P.O. BOX 5555  
MADISON, WI 53705  
(608) 277-7777



- Additional investigation of the area north of the existing building where high soil gas readings were observed is recommended. Shallow soil borings and soil/groundwater sampling could be used in this area to determine the extent of potential contamination.
- Contaminated soils stockpiled on the property should be disposed of properly. This would involve testing of the soils using Toxicity Characteristic Leaching Procedure (TCLP) methods to evaluate disposal options. Discussions with waste disposal companies may be necessary to determine if the soils will be accepted as non-hazardous waste, or will require treatment as hazardous waste.
- A meeting with IEPA to discuss the results of the investigation and the proposed recommendations for additional work should be conducted prior to initiating further work.

The generalized scope of the follow-up investigation (Phase 2) would include completion of five soil borings. Three borings would be located in the vicinity of soil gas sampling location SG9, SG10, and north of the loading dock to investigate the north area of the existing building. If VOCs are detected north of the building, these borings may be instrumented with monitoring wells. Two soil borings would be instrumented with monitoring wells south of soil boring SG1 and west of soil boring SG2 to monitor groundwater near the excavation area.


Soil and groundwater samples would be obtained from each boring. Soil sample depths would be based on qualitative results of photoionization detector (PID) screening of soil samples collected during drilling. Selected soil samples would be analyzed for VOCs and lead. Groundwater samples would be analyzed for VOCs.

After reviewing your comments on the draft report, we will finalize the report for submittal to the IEPA for review. We would like to meet with you to discuss the results of the investigation prior to meeting with IEPA. The meeting with IEPA will be primarily to reach an agreement on the course of action that needs to be taken at the site.

Please call if you have questions or comments regarding the report or the recommendations.

Sincerely,

WARZYN ENGINEERING INC.

  
Richard K. Hosfeld, CPG  
Project Manager

PFJ/vlr/KJQ/DWH  
[wpmisc-110a-76]  
15275.00-MD

Enclosure: Site Investigation Report

Site Investigation  
North American Tool Corporation  
South Beloit, Illinois

November 1990

## TABLE OF CONTENTS

	<u>Page No.</u>
INTRODUCTION .....	1
WORK PERFORMED .....	1
Soil Gas Survey .....	2
Groundwater and Soil Sampling .....	3
Location and Elevation Survey .....	3
Excavation Of Contaminated Soils .....	4
Vapor Venting System .....	4
RESULTS .....	5
Geology and Hydrogeology .....	5
Analytical Results .....	5
Soils .....	5
Groundwater .....	6
CONCLUSIONS .....	7
REFERENCES .....	8

## TABLES

Table 1 - Soil Gas Survey Results  
Table 2 - Groundwater Sampling Results Summary  
Table 3 - Soil Sampling Results Summary  
Table 4 - Well Information Summary

## FIGURES

Figure B1 - Site Features Map

## APPENDICES

Appendix A - Analytical Results



**SITE INVESTIGATION**  
**NORTH AMERICAN TOOL CORPORATION**

**INTRODUCTION**

This report summarizes the site investigation performed by Warzyn Engineering Inc. (Warzyn) for North American Tool Corporation (NATCo). The site is located in the S.E. 1/4 of Sec. 6, T46N, R2E, City of South Beloit, Winnebago County, Illinois. A machine shop was operated at the site for approximately 26 years by the previous owner(s). The site was purchased by Magnetic Data Carriers Corporation from Hanson General Products during a bankruptcy sale in April 1986 but was never occupied. NATCo acquired the site in November 1986. Four monitoring wells were installed for the bankruptcy trustees by Rapp and Associates of Springfield, Illinois, and sampled in December 1987. Results indicated tetrachloroethene (PCE) was present in the groundwater at concentrations ranging from 1.4 to 5.8 ug/L. Three wells remain on the site property. One well reportedly was destroyed when a portion of the property was transferred to Trenwyth Industries Midwest Inc. (date unknown). Recently, NATCo began construction of a building addition located west of the existing building.

The objectives of the site investigation were to examine the extent and magnitude of contamination at the site, and provide recommendations for additional work or other response actions to address the site contamination.

**WORK PERFORMED**

The site investigation generally followed the approach outlined in Warzyn's August 20, 1990 site investigation proposal. The basic approach was outlined to the Illinois Environmental Protection Agency (IEPA) during an August 27, 1990 meeting with NATCo, and the IEPA offered no objection to proceeding with the investigation. The site investigation consisted of the following tasks:

- soil gas survey;
- groundwater and soil sampling;
- location and elevation survey of existing wells;
- excavation of contaminated soils; and
- installation of passive vapor venting system.

Based on initial soil gas survey results, proposed soil borings were not performed due to the limited area of potential contamination. Rather, soil from the contaminated area was excavated and stockpiled at the site.

### SOIL GAS SURVEY

Fourteen soil gas samples were collected in the vicinity of the existing building and the building addition on August 29, 1990 to identify potential areas of volatile organic compound (VOC) contamination. Sampling locations are shown on Drawing 15275-B1. Soil gas sampling results are presented in Appendix A and summarized in Table 1.

Soil gas samples were obtained by driving a rod into the soil to a depth of 3 ft, withdrawing the rod, inserting a sample probe into the hole, and sealing the probe at the ground surface. An air pump was used to draw soil gas through the probe and into a sample vial attached in series between the probe and the pump. The system was purged for approximately 2 minutes prior to obtaining a sample. Following collection, a photoionization detector (HNU meter) was used to screen samples for the presence of VOCs and to help direct the survey. If positive readings were observed, the system was purged with ambient air for one minute prior to sampling the next location. Sample vials were wrapped in foil and stored in the dark on ice until delivered to Warzyn's Analytical Laboratory. The samples were analyzed for 1,1-dichloroethene (1,1-DCE), cis-1,2-dichloroethene (1,2-DCE), trichloroethene (TCE), and tetrachloroethene (PCE) (refer to Appendix A).

### GROUNDWATER AND SOIL SAMPLING

On August 30, 1990, the three existing monitoring wells were redeveloped and sampled for VOC analysis. Water levels were measured on August 30 and again on October 30, 1990. A soil sample collected from a depth of 1-1.5 ft from soil gas sampling location SG03 was also obtained for VOC analysis. Analytical results are presented in Appendix A and summarized in Tables 2 and 3. Soil borings were not performed as originally proposed, because results of the soil gas survey were considered sufficient to outline the areas of contamination.

Monitoring wells MW1, MW2 and MW3 were redeveloped on August 30, 1990 by purging 60 gallons of water from each well using a B-K piston pump, while monitoring pH and specific conductance during purging. Stabilization of pH and specific conductance readings was used to evaluate whether sufficient water volume had been withdrawn from the wells. The objective of development was to remove sediment and water which may not be representative of the groundwater from the well prior to sampling. Refer to Table 4 for monitoring well information. Water level and total depth measurements were performed and groundwater samples were then obtained from each well. A field blank, trip blank, and duplicate sample of Well MW3 were also obtained for quality control. A soil sample was obtained from soil gas location SG03 at a depth of 1 to 1.5 ft using a core sampler. All samples were delivered to Warzyn's analytical laboratory for VOC analysis.

### LOCATION AND ELEVATION SURVEY

Locations, and elevations of ground surface and the top of well casing for wells MW1, MW2, and MW3, were surveyed by R.H. Batterman and Company, Inc. on September 28, 1990. Elevations were measured to the nearest 0.01 ft. Locations were measured to the nearest 0.1 ft. These data were used in conjunction with the water level data to provide groundwater elevations (Refer to Table 4).

### EXCAVATION OF CONTAMINATED SOILS

Excavation of the contaminated soils on the west side of the existing building was performed on September 10, 1990 by Selvog Excavating Inc., with oversight and monitoring by Warzyn. The excavation was centered around soil gas location SG03. The excavation was approximately 43 ft by 18 ft by 5 ft deep (Drawing 15275-B1).

The excavation was performed using a backhoe. Topsoil was removed to a depth of approximately 1 ft. As the soils were removed, the soil in each backhoe bucket was screened with an HNu PID (11.7 eV). Clean material (no readings above background) was segregated from contaminated soil (readings above background). Contaminated soil was stockpiled on plastic.

HNu readings were also used to determine the lateral limits of the excavation (Drawing 15275-B1). The soils exhibited readings of 40-50 ppm near soil gas location SG03, with slight or no readings above background at the excavation boundaries. At a depth of 5 ft, soils from the excavation floor continued to have HNu readings up to 100-160 ppm. Analytical samples were collected at each of the four corners of the excavation. A composite sample of the excavated contaminated soil was also collected for analysis. A hole approximately 6-ft by 6-ft was also excavated in the vicinity of soil gas location SG03 to a depth of approximately 7 ft. Groundwater rose in the excavation to 6.5 ft below ground surface. A water sample was collected and preserved with 1:1 HCl. Samples were analyzed for VOCs at Warzyn's analytical laboratory.

### VAPOR VENTING SYSTEM

A passive vapor venting system was installed beneath the building expansion. The system consists of a perforated PVC pipe surrounded by a granular filter, which runs through the excavated area and is vented to the building exterior. The purpose of the system is to control any potential migration of contaminated soil gas into the building addition. The system was conceptually outlined by Warzyn and reportedly installed by the building contractor who constructed the building addition. No engineering plans were prepared for this system.

## RESULTS

### GEOLOGY AND HYDROGEOLOGY

Soils in the vicinity of SG03 observed during the excavation consisted of topsoil, underlain by black silt with little fine sand (ML, United Soil Classification System) from a depth of 1 to 5 ft. Gray sandy clay (CL) is present from 5 to 6 ft below ground surface with light brown gravelly sand (SP-GP) present to at least 7 ft below ground surface. Regional information indicates that alluvium or windblown sand deposits underlain by sand and gravel associated with the Rock River are present in the area (Berg, et. al. 1984). Boring logs for the site wells are not available.

Water level data collected on August 30 and October 30, 1990 indicates that the water table is within approximately 2 to 5 ft of the ground surface. The monitoring wells are approximately 20 to 21 ft deep (from ground surface), but other construction details or boring logs are not available. Based on the soils observed during excavation, the water table is probably within the upper sandy clay or the underlying gravelly sand. The water table is relatively flat (Drawing 15275-B1) with a gradient of 0.0005 and flow to the southwest. Due to the minimum of wells to determine groundwater flow direction, this estimate of flow direction and gradient should be considered preliminary. The locations of private or municipal water supply wells downgradient of the site have not been determined at this time.

### ANALYTICAL RESULTS

#### Soils

Analytical results of the soil gas samples indicate the presence of two distinct zones of contamination west of the existing building (i.e., sample points SG03 and SG04) and north of the building (SG09 and SG10) (See Drawing 15275-B1 and Table 1). The sample at SG03 had the highest concentration of total VOCs, although SG09 and SG10 had similar concentrations of tetrachloroethene and trichloroethene (SG10, only). VOCs were not detected at the other 10 locations.



Analytical results of the soil samples from soil gas location SG03 (SB03), the four corners of the excavation, and the composite sample of excavated soils are summarized in Table 3. Soil Sample SB03 contained 1,1,1-trichloroethane (TCA) and trichloroethene (TCE) at 422 ug/kg and 214 ug/kg, respectively, with PCE at or below the quantitation limit of 50 ug/kg (Table 3).

The only quantifiable detects in the corner samples were TCA and TCE. TCA was present in three of four corner samples, at concentrations approximately 10 times less than concentrations present in the excavated soil composite sample (TCA; 1570 ug/kg).

The primary organic compounds detected in the excavated soil composite sample were total xylenes at a concentration of 14,600 ug/kg. Total xylenes also were detected in the northeast corner sample at a concentration below the method quantitation limit of 50 ug/l. Ethylbenzene and 1,2-dichlorobenzene and were only observed in the excavated soil composite sample at concentrations of 806 ug/kg and 1450 ug/kg, respectively. The excavation sample was also analyzed for total lead and RCRA characteristics (flashpoint, paint filter test, pH, and total solids). Lead was observed at 46.0 mg/kg. The flashpoint was greater than 200° F, the paint filter test indicated 0% free liquids, the pH was 6.87 S.U., and the total solids were 86.1%.

#### Groundwater

VOCs were detected in each of the three wells, with largest number of individual contaminants observed at well MW-2. However, none of the concentrations exceed the groundwater quality criteria specified in the recently proposed Title 35, Section 620.301 of the Illinois Administrative Code (Title 35)(Table 2). Tetrachloroethene (PCE), the compound of concern based on previous 1987 sampling, was detected at similar concentrations at each of the three wells (1.10 ug/L to 2.2 ug/L).

The groundwater sample from the excavation in vicinity of soil gas location SG03 had concentrations of 9150 ug/L TCA and 1180 ug/L of 1,1-DCE. These concentrations exceed the proposed Title 35 groundwater quality criteria for these compounds.

None of the three wells are known to be directly downgradient of the excavation area, based on limited water level data. The distribution of VOCs in all three monitoring wells which surround the excavated area (Drawing 15275-B1) may be the result of changes in groundwater flow direction or gaseous diffusion in the unsaturated zone. Small changes in groundwater elevations could change the groundwater flow direction because the water table is relatively flat. Alternatively, volatile compounds could be transported via diffusion in the unsaturated soils, particularly if portions of the gravelly sand are unsaturated and overlain by a clayey sand which may limit release of VOCs to the atmosphere. Also, VOCs at well MW1 may be related to the localized occurrence of VOCs in the soil gas at soil gas sampling location SG10.

### CONCLUSIONS

The site investigation succeeded in determining the extent and magnitude of soil contamination at the site, and provided the basis for excavation of the contaminated soil in the area west of the existing building. The following observations and conclusions are based on results of the site investigation.

- VOCs in soil appear limited to relatively small areas immediately west and north of the existing building based on the soil gas survey.
- Contaminated soil was excavated from the area west of the building to a depth of 5 ft, and stockpiled on-site. The excavation removed unsaturated soils with VOCs over 0.5 ppm, leaving soils with VOCs less than 0.5 ppm.
- VOCs in groundwater have been detected in wells MW1, MW2, and MW3, and beneath the excavation. Detected contaminants were chlorinated ethane and ethene compounds. Proposed Title 35 groundwater quality criteria were not exceeded at the existing site monitoring wells. A groundwater sample collected from the excavation did exceed the proposed Title 35 standards for 1,1,1-trichloroethane and 1,1-dichloroethene.

- The water table in the vicinity of the site is relatively flat based on available water level measurements. Groundwater flow is apparently toward the southwest. Changes in groundwater flow direction, or gaseous diffusion in the unsaturated zone, may account for the presence of VOCs in samples from the three monitoring wells surrounding the areas of potential VOC contamination.

#### REFERENCES

Berg, R.C. Kempton, J.P., and Stencyk, A.N. (1984) Geology for Planning in Boone and Winnebago Counties, Illinois Department of Energy and Natural Resources, State Geological Survey Division, Circular 531.

**Appendix A**  
**Analytical Results**

TABLE 1

Soil Gas Survey Results  
North American Tool Corporation  
South Beloit, Illinois

Soil Gas Sampling Location	Field Screening With HNu ppm(1)	Laboratory Analytical Results	
		Compound(2)	Concentration (ug/L of soil gas)
SG01	ND	ND	-
SG02	ND	ND	-
SG03	11-15 (11-15)	1,1-Dichloroethene	119 (118)
		cis-1,2-Dichloroethene	514 (499)
		Trichloroethene	17.3 (20.9)
		Tetrachloroethene	15.0 (17.8)
SG04	ND	cis-1,2-Dichloroethene	1.04
SG05	ND	ND	-
SG06	ND	ND	-
SG07	0.5	ND	-
SG08	ND	ND	-
SG09	3.0	Trichloroethene	<1.00
		Tetrachloroethene	36.4
SG10	1.0	1,1-Dichloroethene	3.61
		cis-1,2-Dichloroethene	84.5
		Trichloroethene	18.0
		Tetrachloroethene	27.2
SG11	1.0	ND	-
SG12	0.8	ND	-
SG13	0.5	ND	-
SG14	NA	ND	-

NOTES:

ND = No Detects

NA = Not Analyzed

&lt;1.00 indicates concentration below method quantitation limit of 1.00 ug/L soil gas.

(1) ppm total volatile organics above background (reported as benzene equivalent)

(2) Sample chromatograms for soil gas samples SG03, SG04, SG09 and SG10 also contain unidentified compounds.

(3) Concentrations in parenthesis are from SG03 duplicate sample.

PFJ/vlr/APA/KJQ

[jlv-403-90]

15275.00-MD



TABLE 2

Groundwater Sampling Results Summary  
North American Tool Corporation  
South Beloit, Illinois

<u>Location</u>	<u>Compound</u>	<u>Concentration</u> (ug/L)	<u>Groundwater(3)</u> <u>Quality Criteria</u> (ug/L)
MW1	Tetrachloroethene	1.18	5
MW2	1,1-Dichloroethane	16.5	-
	1,1-Dichloroethene	2.15	7
	cis-1,2-Dichloroethene	4.91	70
	Tetrachloroethene	1.10	5
	1,1,1-Trichloroethane	66.3	200
	Trichloroethene	3.28	5
MW3	Tetrachloroethene	2.23 (1.78)	5
	1,1,1-Trichloroethane	1.25 (1.14)	200
Excavation Ground- water	1,1-Dichloroethene	1180	7
	1,1,1-Trichloroethane	9150	200

NOTES:

1. Sampling performed on August 30, 1990.
2. ( ) concentrations indicate results of duplicate sample (MW3 Dup) analysis.
3. Groundwater quality criteria from Title 35, Section 620.301, Illinois Administrative Code. (same as maximum concentration levels; U.S. EPA office of Drinking Water, April 1990 for those compounds)
4. - indicates standard not available for this compound

PFJ/vlr/APA/KJQ  
[jlv-403-89]  
15275-MD

TABLE 3

Soil Sampling Results Summary  
North American Tool Corporation  
South Beloit, Illinois

Sample Location (1)Q	Sample Depth (ft) 1-1.5	Compound	Concentration (ppm)
SB 03		Tetrachloroethene	<0.050
		1,1,1-Trichloroethane	0.422
		Trichloroethene	0.214
NE	—	1,1,1-Trichloroethane	0.129
		Trichloroethene	0.0526
		Xylenes	<0.050
NW	—	Toluene	<0.050
		1,1,1-Trichloroethane	0.135
		Trichloroethene	<0.050
SE	—	Toluene	<0.050
SW	—	Toluene	<0.050
		1,1,1-Trichloroethane	0.0673
Excavated Soil		1,2-Dichlorobenzene	1.450
		1,2-Dichloroethane	<0.050
		Ethyl Benzene	0.806
		Tetrachloroethene	1.240
		1,1,1-Trichloroethane	1.570
		Xylenes	14.600
		(2), (3)	

<.050 = detected below quantitation limit of .050 mg/kg.

(1) Samples obtained from SB03, and from the NE, NW, SE and SW corners of the soil excavation (Refer to Drawing 15275-B1)

(2) Unidentified compounds also detected

(3) Sample also analyzed for total petroleum hydrocarbons (TPH). Sample contains unknown hydrocarbons. Estimated concentration of TPH is 2190 mg/kg, based on the gasoline standard.

PFJ/vlr/APA/KJQ  
[Jlv-403-88]  
15275.00-MD

TABLE 4


Well Information Summary  
North American Tool Corporation  
South Beloit, Illinois

WELL REDEVELOPMENT, AUGUST 30, 1990												
Well	Ground(2) Elev. (ft MSL)	TOC(1) Elev. (ft MSL)	August 30, 1990		Groundwater Elev. (ft MSL)	October 30, 1990		Gallons Purged	pH(S.U.)	Conductivity (umoh/cm)	Temperature (°C)	Comments
			Total Well(1) Depth TOC (ft)	Depth to(1) Water Level TOC (ft)		Depth to (1) Water (ft)	Groundwater Elev. (ft MSL)					
HW1	736.83	739.35	23.1	7.18	732.17	7.37	731.98	15 35 60	6.71 6.85 6.71	640 640 640	16 16 16	Brown Lt Brown Clear
HW2	735.86	738.03	23.2	6.08	731.95	6.24	731.79	15 35 60	6.79 6.69 6.76	630 610 610	17 17 17	Dark Brown Lt Brown Clear, sandy turbidity
HW3	734.92	736.67	22.6	4.07	732.60	4.93	731.74	15 35 60	6.73 6.70 6.72	490 490 490	14 13.5 13.5	Light Brown sandy Light Brown Very Light Brown

## Notes:


1. Depths measured from top of well casing.
2. ft MSL indicates ft above Mean Sea Level

S.U. = standard units



- LEGEND**
- ⊕ SG1 SOIL GAS SAMPLING LOCATION AND NUMBER
  - SB3 SOIL SAMPLING LOCATION AND NUMBER
  - ⊕ MW1 MONITORING WELL LOCATION, NUMBER AND WATER TABLE ELEVATION (731.98)

- NOTES**
1. BASE MAP DEVELOPED FROM PLAT OF SURVEY PROVIDED BY R.H. GERRARD & SONS, INC. DATED NOVEMBER 22, 1880, REVISED OCTOBER 1, 1890.
  2. SOIL GAS SURVEY AND SOIL SAMPLING PERFORMED BY WARZYN ENGINEERING INC. ON AUGUST 25-30, 1990.
  3. SOIL SAMPLES FROM THE FOUR CORNERS OF THE 5 FT. DEEP EXCAVATION (APPROXIMATELY 18 FT. X 43 FT.) OBTAINED BY WARZYN ENGINEERING INC. ON SEPTEMBER 10, 1990.
  4. WITHIN THE EXCAVATION, A 5 FT. X 6 FT. AREA AROUND SG1 WAS EXCAVATED TO A DEPTH OF 7 FT., AND THE GROUNDWATER WAS SAMPLED BY WARZYN ENGINEERING INC. ON SEPTEMBER 10, 1990.
  5. WATER LEVEL MEASUREMENTS PERFORMED ON OCTOBER 29, 1990 BY WARZYN ENGINEERING INC.



 15275 <b>B1</b>	<b>SITE FEATURES MAP</b> SITE INVESTIGATION NORTH AMERICAN TOOL CORPORATION SOUTH BELOIT, WINNEBAGO CO., ILLINOIS		<b>WARZYN</b> WARZYN ENGINEERING, INC.		Drawn By: <i>JE</i> Checked By: <i>PFF</i> Date: <i>11-9-90</i>
	1 OF 1 15275		Approved By: <i>Richard H. Hefner</i>		Reference:
	15275		15275		15275
	15275		15275		15275



MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 2 OF 9  
CK'D: ~~SW~~ APP'D: KAS  
DATE ISSUED: 8/29/90

COMPOUND	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS)	1609-003(1) SG-03 8/29/90	1609-004(1) SG-03 DUP 8/29/90
=====	=====	=====	=====
1,1-DICHLOROETHENE	1.00	119	118
CIS-1,2-DICHLOROETHENE	1.00	514	499
TRICHLOROETHENE	1.00	17.3	20.9
TETRACHLOROETHENE	1.00	15.0	17.8

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

(1) SAMPLE CHROMATOGRAM CONTAINS UNIDENTIFIED COMPOUNDS.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.





MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 3 OF 9  
CK'D: *sw* APP'D: *KDJ*  
DATE ISSUED: 9/29/90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS) =====	1609-005	1609-006(1)
		SG-FIELD BLANK 8/29/90 =====	SG-04 8/29/90 =====
1,1-DICHLOROETHENE	1.00	X	X
CIS-1,2-DICHLOROETHENE	1.00	X	1.04
TRICHLOROETHENE	1.00	X	X
TETRACHLOROETHENE	1.00	X	X

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

(1) SAMPLE CHROMATOGRAM CONTAINS UNIDENTIFIED COMPOUNDS.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.

WARZYN

MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 4 OF 7  
CK'D: *mm* APP'D: *KDS*  
DATE ISSUED: 9/24/90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS) =====	1609-007 SG-05 8/29/90 =====	1609-008 SG-06 8/29/90 =====
1,1-DICHLOROETHENE	1.00	X	X
CIS-1,2-DICHLOROETHENE	1.00	X	X
TRICHLOROETHENE	1.00	X	X
TETRACHLOROETHENE	1.00	X	X

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.



VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 5 OF 9  
CK'D: *mm* APP'D: KDJ  
DATE ISSUED: 2/24/90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS) =====	1609-009 SG-07 8/29/90 =====	1609-010 SG-08 8/29/90 =====
1,1-DICHLOROETHENE	1.00	X	X
CIS-1,2-DICHLOROETHENE	1.00	X	X
TRICHLOROETHENE	1.00	X	X
TETRACHLOROETHENE	1.00	X	X

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.

WARZYN

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 6 OF 7  
CK'D: *awh* APP'D: *kos*  
DATE ISSUED: 8/29/90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS) =====	1609-011(1) SG-09 8/29/90 =====	1609-012(1) SG-10 8/29/90 =====
1,1-DICHLOROETHENE	1.00	X	3.61
CIS-1,2-DICHLOROETHENE	1.00	X	84.5
TRICHLOROETHENE	1.00	BMQL	18.0
TETRACHLOROETHENE	1.00	36.4	27.2

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

(1) SAMPLE CHROMATOGRAM CONTAINS UNIDENTIFIED COMPOUNDS.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.



VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 7 OF 9  
CK'D: *sm* APP'D: *kos*  
DATE ISSUED: 9/24/90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS) =====	1609-013 SG-11 8/29/90 =====	1609-014 SG-12 8/29/90 =====
1,1-DICHLOROETHENE	1.00	X	X
CIS-1,2-DICHLOROETHENE	1.00	X	X
TRICHLOROETHENE	1.00	X	X
TETRACHLOROETHENE	1.00	X	X

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.



WARZYN

MADISON  
ONE SCIENCE CENTER  
P.O. BOX 537  
MADISON, WI 53703  
(608) 231-4777  
FAX (608) 231-4778

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 7 OF 9  
CK'D: *mm* APP'D: *KDJ*  
DATE ISSUED: 9/24/90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS) =====	1609-015 SG-13 8/29/90 =====	1609-016 SG-14 8/29/90 =====
1,1-DICHLOROETHENE	1.00	X	X
CIS-1,2-DICHLOROETHENE	1.00	X	X
TRICHLOROETHENE	1.00	X	X
TETRACHLOROETHENE	1.00	X	X

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.

WARZYN

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 9 OF 9  
CK'D: *mw* APP'D: *KDJ*  
DATE ISSUED: 9/24/90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS) =====	1609-017 TRIP BLANK 8/29/90 =====
1,1-DICHLOROETHENE	1.00	X
CIS-1,2-DICHLOROETHENE	1.00	X
TRICHLOROETHENE	1.00	X
TETRACHLOROETHENE	1.00	X

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.



CHAIN OF CUSTODY RECORD

PROJ. NO.	PROJECT NAME	NO. OF CONTAINERS	REMARKS
15275-00	NATC <sub>6</sub>		
LOCATION: South Beloit, Ill			
SAMPLERS: (Signature)			
Thomas J. Drahok			
LAB NO.	DATE	TIME	STATION/LOCATION
1601	8/29/90	0900	Trip Blank
1602	8/29/90	1245	SG-01
1603	8/29/90	1300	SG-02
1604	8/29/90	1315	SG-03
1605	8/29/90	1330	SG-03 DUP
1606	8/29/90	1330	SG-Field Blank
1607	8/29/90	1355	SG-04
1608	8/29/90	1410	SG-05
1609	8/29/90	1420	SG-06
1610	8/29/90	1435	SG-07
1611	8/29/90	1445	SG-08
1612	8/29/90	1510	SG-09
1613	8/29/90	1530	SG-10
Relinquished by: (Signature) Thomas J. Drahok			
Received by: (Signature)			
Date / Time 8/29/90 1810			
Relinquished by: (Signature)			
Received by: (Signature)			
Date / Time			
Relinquished by: (Signature)			
Received by: (Signature)			
Date / Time 8/30/90 7:00 AM			
PROJECT MANAGER: R. Hostfeld			

Remarks

SOIL GAS ANALYSIS - CHLORINATED HYDROCARBONS

[illegible]

Remarks

SOL GAS ANALYSIS - CH202417 - 3/24/2024

WARZYN

MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 1 OF 2  
CK'D: BUT APP'D: KDJ  
DATE ISSUED: 9-26-90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/KG AS REC'D) =====	1623-001(1) SB-03 8/30/90 =====
BENZENE	25.0	X
BROMOCHLOROMETHANE	50.0	X
BROMODICHLOROMETHANE	50.0	X
BROMOFORM	50.0	X
BROMOMETHANE	50.0	X
CARBON TETRACHLORIDE	50.0	X
CHLOROBENZENE	50.0	X
CHLORODIBROMOMETHANE	50.0	X
CHLOROETHANE	50.0	X
2-CHLOROETHYL VINYL ETHER	500	X
CHLOROFORM	50.0	X
CHLOROMETHANE	50.0	X
1,2-DIBROMO-3-CHLOROPROPANE	100	X
1,2-DICHLOROBENZENE	50.0	X
1,3-DICHLOROBENZENE	50.0	X
1,4-DICHLOROBENZENE	50.0	X
1,1-DICHLOROETHANE	50.0	X
1,2-DICHLOROETHANE	50.0	X
1,1-DICHLOROETHENE	50.0	X
CIS-1,2-DICHLOROETHENE	50.0	X
TRANS-1,2-DICHLOROETHENE	50.0	X
1,2-DICHLOROPROPANE	50.0	X
CIS-1,3-DICHLOROPROPENE	50.0	X
TRANS-1,3-DICHLOROPROPENE	50.0	X
ETHYL BENZENE	50.0	X
METHYLENE CHLORIDE	250	X
1,1,1,2-TETRACHLOROETHANE	50.0	X
1,1,2,2-TETRACHLOROETHANE	50.0	X
TETRACHLOROETHENE	50.0	BMQL
TOLUENE	50.0	X
1,1,1-TRICHLOROETHANE	50.0	422
1,1,2-TRICHLOROETHANE	50.0	X
TRICHLOROETHENE	50.0	214
TRICHLOROFLUOROMETHANE	50.0	X
VINYL CHLORIDE	50.0	X
XYLENES	50.0	X



WARZYN

MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 1 OF 4  
CK'D: ~~BUY~~ APP'D: KCS  
DATE ISSUED: 9-26-90

COMPOUND	REPORTABLE DETECTION LIMIT (UG/L)	1623-002 MW-1 8/30/90	1623-003 MW-2 8/30/90	1623-004 MW-3 8/30/90
=====	=====	=====	=====	=====
BENZENE	1.00	X	X	X
BROMOCHLOROMETHANE	1.00	X	X	X
BROMODICHLOROMETHANE	1.00	X	X	X
BROMOFORM	1.00	X	X	X
BROMOMETHANE	1.00	X	X	X
CARBON TETRACHLORIDE	1.00	X	X	X
CHLOROBENZENE	1.00	X	X	X
CHLORODIBROMOMETHANE	1.00	X	X	X
CHLOROETHANE	1.00	X	X	X
2-CHLOROETHYL VINYL ETHER	10.0	X	X	X
CHLOROFORM	1.00	X	X	X
CHLOROMETHANE	1.00	X	X	X
1,2-DIBROMO-3-CHLOROPROPANE	2.00	X	X	X
1,2-DICHLOROBENZENE	1.00	X	X	X
1,3-DICHLOROBENZENE	1.00	X	X	X
1,4-DICHLOROBENZENE	1.00	X	X	X
1,1-DICHLOROETHANE	1.00	X	16.5	X
1,2-DICHLOROETHANE	1.00	X	X	X
1,1-DICHLOROETHENE	1.00	X	2.15	X
CIS-1,2-DICHLOROETHENE	1.00	X	4.91	X
TRANS-1,2-DICHLOROETHENE	1.00	X	X	X
1,2-DICHLOROPROPANE	1.00	X	X	X
CIS-1,3-DICHLOROPROPENE	1.00	X	X	X
TRANS-1,3-DICHLOROPROPENE	1.00	X	X	X
ETHYL BENZENE	1.00	X	X	X
METHYLENE CHLORIDE	5.00	X	X	X
1,1,1,2-TETRACHLOROETHANE	1.00	X	X	X
1,1,2,2-TETRACHLOROETHANE	1.00	X	X	X
TETRACHLOROETHENE	1.00	1.18	1.10	2.23
TOLUENE	1.00	X	X	X
1,1,1-TRICHLOROETHANE	1.00	X	66.3	1.25
1,1,2-TRICHLOROETHANE	1.00	X	X	X
TRICHLOROETHENE	1.00	X	3.28	X
TRICHLOROFLUOROMETHANE	1.00	X	X	X
VINYL CHLORIDE	1.00	X	X	X
XYLENES	1.00	X	X	X

WARZYN

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 2 OF 4  
CK'D: ~~BY~~ APP'D: KCS  
DATE ISSUED: 9-26-90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L) =====	1623-005 MW-3 DUP 8/30/90 =====
BENZENE	1.00	X
BROMOCHLOROMETHANE	1.00	X
BROMODICHLOROMETHANE	1.00	X
BROMOFORM	1.00	X
BROMOMETHANE	1.00	X
CARBON TETRACHLORIDE	1.00	X
CHLOROBENZENE	1.00	X
CHLORODIBROMOMETHANE	1.00	X
CHLOROETHANE	1.00	X
2-CHLOROETHYL VINYL ETHER	10.0	X
CHLOROFORM	1.00	X
CHLOROMETHANE	1.00	X
1,2-DIBROMO-3-CHLOROPROPANE	2.00	X
1,2-DICHLOROBENZENE	1.00	X
1,3-DICHLOROBENZENE	1.00	X
1,4-DICHLOROBENZENE	1.00	X
1,1-DICHLOROETHANE	1.00	X
1,2-DICHLOROETHANE	1.00	X
1,1-DICHLOROETHENE	1.00	X
CIS-1,2-DICHLOROETHENE	1.00	X
TRANS-1,2-DICHLOROETHENE	1.00	X
1,2-DICHLOROPROPANE	1.00	X
CIS-1,3-DICHLOROPROPENE	1.00	X
TRANS-1,3-DICHLOROPROPENE	1.00	X
ETHYL BENZENE	1.00	X
METHYLENE CHLORIDE	5.00	X
1,1,1,2-TETRACHLOROETHANE	1.00	X
1,1,2,2-TETRACHLOROETHANE	1.00	X
TETRACHLOROETHENE	1.00	1.78
TOLUENE	1.00	X
1,1,1-TRICHLOROETHANE	1.00	1.14
1,1,2-TRICHLOROETHANE	1.00	X
TRICHLOROETHENE	1.00	X
TRICHLOROFLUOROMETHANE	1.00	X
VINYL CHLORIDE	1.00	X
XYLENES	1.00	X

WARZYN

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 3 OF 4  
CK'D: BUA APP'D: KCS  
DATE ISSUED: 9-26-90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L) =====	1623-006 FIELD BLANK 8/30/90 =====	1623-007 TRIP BLANK 8/30/90 =====
BENZENE	1.00	X	X
BROMOCHLOROMETHANE	1.00	X	X
BROMODICHLOROMETHANE	1.00	X	X
BROMOFORM	1.00	X	X
BROMOMETHANE	1.00	X	X
CARBON TETRACHLORIDE	1.00	X	X
CHLOROBENZENE	1.00	X	X
CHLORODIBROMOMETHANE	1.00	X	X
CHLOROETHANE	1.00	X	X
2-CHLOROETHYL VINYL ETHER	10.0	X	X
CHLOROFORM	1.00	X	X
CHLOROMETHANE	1.00	X	X
1,2-DIBROMO-3-CHLOROPROPANE	2.00	X	X
1,2-DICHLOROBENZENE	1.00	X	X
1,3-DICHLOROBENZENE	1.00	X	X
1,4-DICHLOROBENZENE	1.00	X	X
1,1-DICHLOROETHANE	1.00	X	X
1,2-DICHLOROETHANE	1.00	X	X
1,1-DICHLOROETHENE	1.00	X	X
CIS-1,2-DICHLOROETHENE	1.00	X	X
TRANS-1,2-DICHLOROETHENE	1.00	X	X
1,2-DICHLOROPROPANE	1.00	X	X
CIS-1,3-DICHLOROPROPENE	1.00	X	X
TRANS-1,3-DICHLOROPROPENE	1.00	X	X
ETHYL BENZENE	1.00	X	X
METHYLENE CHLORIDE	5.00	X	X
1,1,1,2-TETRACHLOROETHANE	1.00	X	X
1,1,2,2-TETRACHLOROETHANE	1.00	X	X
TETRACHLOROETHENE	1.00	X	X
TOLUENE	1.00	X	X
1,1,1-TRICHLOROETHANE	1.00	X	X
1,1,2-TRICHLOROETHANE	1.00	X	X
TRICHLOROETHENE	1.00	X	X
TRICHLOROFLUOROMETHANE	1.00	X	X
VINYL CHLORIDE	1.00	X	X
XYLENES	1.00	X	X

WARZYN

M  
ONE SCIENCE  
P.O. B.  
MADISON, WI  
(608) 2  
FAX (608) 2

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 4 OF 4  
CK'D: ~~BU~~ APP'D: ~~205~~  
DATE ISSUED: 9-26-90

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.

# CHAIN OF CUSTODY RECORD

PROJ. NO.		PROJECT NAME		NO. OF CONTAINERS		REMARKS	
15275.00		NATCO					
LOCATION: South Beloit IL							
SAMPLERS: (Signature)							
LAB. NO.	DATE	TIME	STATION	LOCATION	VOC's (Gal/Coz)	VOC's (Gal/Coz)	
1623-001	8/30/90	0900	Tri-p	Blank	✓		Vials pres. w/ HC-1
1623-002	8/30/90	1500	MW-1		✓		
1623-003	8/30/90	1525	MW-2		✓		
1623-004	8/30/90	1540	Field	Blank	✓		
1623-005	8/30/90	1555	MW-3		✓		
1623-006	8/30/90	↓	MW-3	DUP	✓		
1623-007	8/30/90	1430	SB-03		✓		1-1.5 Feet
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time	
Sharon J. Dushak		8/30/90 1830					
Relinquished by: (Signature)		Date / Time		Received by: (Signature)		Date / Time	
Relinquished by: (Signature)		Date / Time		Received for Laboratory by: (Signature)		Date / Time	
				Sharon J. Dushak		8/31/90 8:15 AM	
Remarks		PROJECT MANAGER: R. Hosfeld					

samples delivered to walk in cooler, received intact

WARZYN

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NATCO  
LOCATION: SOUTH BELOIT, ILLINOIS  
C#: 15275.00

PAGE 1 OF 9  
CK'D: *mm* APP'D: *KJS*  
DATE ISSUED: 9/24/90

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L OF SOIL GAS) =====	1609-001 SG-01 8/29/90 =====	1609-002 SG-02 8/29/90 =====
1,1-DICHLOROETHENE	1.00	X	X
CIS-1,2-DICHLOROETHENE	1.00	X	X
TRICHLOROETHENE	1.00	X	X
TETRACHLOROETHENE	1.00	X	X

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.



WARZYN

ANALYTICAL LABORATORY RESULTS  
WI LAB CERTIFICATION ID#: 113138300

PROJECT: NORTH AMERICAN TOOL CORP.

PROJECT #: 15275.00

DATE SAMPLED: 9/10/90

LOCATION: S. BELOIT, WISCONSIN

CK'D: KDJ APP'D: KDJ

DATE ISSUED: 10-23-90

LAB NO.

1680-007

SAMPLE DESCRIPTION

EXCAVATION - CONTAMINATED

LEAD, TOTAL

46.0

RCRA CHARACTERISTICS

FLASHPOINT (°F)

>200

PAINT FILTER TEST (%FREE LIQUIDS)

0

PH (S.U.)

6.87

TOTAL SOLIDS (%)

86.1

RESULTS ARE REPORTED IN MG/KG AS RECEIVED UNLESS OTHERWISE STATED.

METHOD REFERENCE: SW-846, "TEST METHODS FOR EVALUATING SOLID WASTE",  
SEPTEMBER, 1986.

METHOD 7420: LEAD

METHOD 9045: PH

METHOD 9095: PAINT FILTER TEST

METHOD 1010: FLASHPOINT

EPA-600, "METHODS FOR CHEMICAL ANALYSIS OF WATER AND  
WASTES", MARCH, 1984.

METHOD 160.3: TOTAL SOLIDS

WARZYN

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NORTH AMERICAN TOOL CORP.  
LOCATION: S. BELOIT, WISCONSIN  
C#: 15275.00

PAGE 1 OF 3  
CK'D KDJ APP'D: KDJ  
DATE ISSUED: 10-23-90

COMPOUND	REPORTABLE DETECTION LIMIT (UG/L)	1680-001 EXCAVATION GROUND WATER 9/10/90
=====	=====	=====
BENZENE	1000	X
BROMOCHLOROMETHANE	1000	X
BROMODICHLOROMETHANE	1000	X
BROMOFORM	1000	X
BROMOMETHANE	1000	X
CARBON TETRACHLORIDE	1000	X
CHLOROBENZENE	1000	X
CHLORODIBROMOMETHANE	1000	X
CHLOROETHANE	1000	X
2-CHLOROETHYL VINYL ETHER	10000	X
CHLOROFORM	1000	X
CHLOROMETHANE	1000	X
1,2-DIBROMO-3-CHLOROPROPANE	2000	X
1,2-DICHLOROBENZENE	1000	X
1,3-DICHLOROBENZENE	1000	X
1,4-DICHLOROBENZENE	1000	X
1,1-DICHLOROETHANE	1000	X
1,2-DICHLOROETHANE	1000	X
1,1-DICHLOROETHENE	1000	1180
CIS-1,2-DICHLOROETHENE	1000	X
TRANS-1,2-DICHLOROETHENE	1000	X
1,2-DICHLOROPROPANE	1000	X
CIS-1,3-DICHLOROPROPENE	1000	X
TRANS-1,3-DICHLOROPROPENE	1000	X
ETHYL BENZENE	1000	X
METHYLENE CHLORIDE	5000	X
1,1,1,2-TETRACHLOROETHANE	1000	X
1,1,2,2-TETRACHLOROETHANE	1000	X
TETRACHLOROETHENE	1000	X
TOLUENE	1000	X
1,1,1-TRICHLOROETHANE	1000	9150
1,1,2-TRICHLOROETHANE	1000	X
TRICHLOROETHENE	1000	X
TRICHLOROFLUOROMETHANE	1000	X
VINYL CHLORIDE	1000	X
XYLENES	1000	X

WARZYN

MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NORTH AMERICAN TOOL CORP.  
LOCATION: S. BELOIT, WISCONSIN  
C#: 15275.00

PAGE 2 OF 3  
CK'D:KDJ APP'D:KDJ  
DATE ISSUED:10-23-92

COMPOUND =====	REPORTABLE DETECTION LIMIT (UG/L) =====	1680-002 TRIP BLANK 9/10/90 =====
BENZENE	1.00	X
BROMOCHLOROMETHANE	1.00	X
BROMODICHLOROMETHANE	1.00	X
BROMOFORM	1.00	X
BROMOMETHANE	1.00	X
CARBON TETRACHLORIDE	1.00	X
CHLOROBENZENE	1.00	X
CHLORODIBROMOMETHANE	1.00	X
CHLOROETHANE	1.00	X
2-CHLOROETHYL VINYL ETHER	10.0	X
CHLOROFORM	1.00	X
CHLOROMETHANE	1.00	X
1,2-DIBROMO-3-CHLOROPROPANE	2.00	X
1,2-DICHLOROBENZENE	1.00	X
1,3-DICHLOROBENZENE	1.00	X
1,4-DICHLOROBENZENE	1.00	X
1,1-DICHLOROETHANE	1.00	X
1,2-DICHLOROETHANE	1.00	X
1,1-DICHLOROETHENE	1.00	X
CIS-1,2-DICHLOROETHENE	1.00	X
TRANS-1,2-DICHLOROETHENE	1.00	X
1,2-DICHLOROPROPANE	1.00	X
CIS-1,3-DICHLOROPROPENE	1.00	X
TRANS-1,3-DICHLOROPROPENE	1.00	X
ETHYL BENZENE	1.00	X
METHYLENE CHLORIDE	5.00	X
1,1,1,2-TETRACHLOROETHANE	1.00	X
1,1,2,2-TETRACHLOROETHANE	1.00	X
TETRACHLOROETHENE	1.00	X
TOLUENE	1.00	X
1,1,1-TRICHLOROETHANE	1.00	X
1,1,2-TRICHLOROETHANE	1.00	X
TRICHLOROETHENE	1.00	X
TRICHLOROFLUOROMETHANE	1.00	X
VINYL CHLORIDE	1.00	X
XYLENES	1.00	X

WARZYN

MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NORTH AMERICAN TOOL CORP.  
LOCATION: S. BELOIT, WISCONSIN  
C#: 15275.00

PAGE 3 OF 3  
CK'D:KDJ APP'D:KDJ  
DATE ISSUED:10-23-90

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING SOLID  
WASTE", SEPTEMBER, 1986. METHODS 8010  
AND 8020 WITH MODIFICATIONS.



MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NORTH AMERICAN TOOL CORP.  
LOCATION: S. BELOIT, WISCONSIN  
C#: 15275.00

PAGE 1 OF 4  
CK'D KDS APP'D: KDS  
DATE ISSUED: 10-23-90

COMPOUND	REPORTABLE DETECTION LIMIT (UG/KG AS REC'D)	1680-003 NORTH EAST EXCAVATION 9/10/90	1680-004 NORTH WEST EXCAVATION 9/10/90
=====	=====	=====	=====
BENZENE	25.0	X	X
BROMOCHLOROMETHANE	50.0	X	X
BROMODICHLOROMETHANE	50.0	X	X
BROMOFORM	50.0	X	X
BROMOMETHANE	50.0	X	X
CARBON TETRACHLORIDE	50.0	X	X
CHLOROBENZENE	50.0	X	X
CHLORODIBROMOMETHANE	50.0	X	X
CHLOROETHANE	50.0	X	X
2-CHLOROETHYL VINYL ETHER	500	X	X
CHLOROFORM	50.0	X	X
CHLOROMETHANE	50.0	X	X
1,2-DIBROMO-3-CHLOROPROPANE	100	X	X
1,2-DICHLOROBENZENE	50.0	X	X
1,3-DICHLOROBENZENE	50.0	X	X
1,4-DICHLOROBENZENE	50.0	X	X
1,1-DICHLOROETHANE	50.0	X	X
1,2-DICHLOROETHANE	50.0	X	X
1,1-DICHLOROETHENE	50.0	X	X
CIS-1,2-DICHLOROETHENE	50.0	X	X
TRANS-1,2-DICHLOROETHENE	50.0	X	X
1,2-DICHLOROPROPANE	50.0	X	X
CIS-1,3-DICHLOROPROPENE	50.0	X	X
TRANS-1,3-DICHLOROPROPENE	50.0	X	X
ETHYL BENZENE	50.0	X	X
METHYLENE CHLORIDE	250	X	X
1,1,1,2-TETRACHLOROETHANE	50.0	X	X
1,1,2,2-TETRACHLOROETHANE	50.0	X	X
TETRACHLOROETHENE	50.0	X	X
TOLUENE	50.0	X	BMQL
1,1,1-TRICHLOROETHANE	50.0	129	135
1,1,2-TRICHLOROETHANE	50.0	X	X
TRICHLOROETHENE	50.0	52.6	BMQL
TRICHLOROFLUOROMETHANE	50.0	X	X
VINYL CHLORIDE	50.0	X	X
XYLENES	50.0	BMQL	X



WARZYN

MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NORTH AMERICAN TOOL CORP.  
LOCATION: S. BELOIT, WISCONSIN  
C#: 15275.00

PAGE 2 OF 4  
CK'D:KDS APP'D:KDS  
DATE ISSUED: 10-23-90

COMPOUND	REPORTABLE DETECTION LIMIT (UG/KG AS REC'D)	1680-005 SOUTH EAST EXCAVATION 9/10/90	1680-006(1) SOUTH WEST EXCAVATION 9/10/90
=====	=====	=====	=====
BENZENE	25.0	X	X
BROMOCHLOROMETHANE	50.0	X	X
BROMODICHLOROMETHANE	50.0	X	X
BROMOFORM	50.0	X	X
BROMOMETHANE	50.0	X	X
CARBON TETRACHLORIDE	50.0	X	X
CHLOROBENZENE	50.0	X	X
CHLORODIBROMOMETHANE	50.0	X	X
CHLOROETHANE	50.0	X	X
2-CHLOROETHYL VINYL ETHER	500	X	X
CHLOROFORM	50.0	X	X
CHLOROMETHANE	50.0	X	X
1,2-DIBROMO-3-CHLOROPROPANE	100	X	X
1,2-DICHLOROBENZENE	50.0	X	X
1,3-DICHLOROBENZENE	50.0	X	X
1,4-DICHLOROBENZENE	50.0	X	X
1,1-DICHLOROETHANE	50.0	X	X
1,2-DICHLOROETHANE	50.0	X	X
1,1-DICHLOROETHENE	50.0	X	X
CIS-1,2-DICHLOROETHENE	50.0	X	X
TRANS-1,2-DICHLOROETHENE	50.0	X	X
1,2-DICHLOROPROPANE	50.0	X	X
CIS-1,3-DICHLOROPROPENE	50.0	X	X
TRANS-1,3-DICHLOROPROPENE	50.0	X	X
ETHYL BENZENE	50.0	X	X
METHYLENE CHLORIDE	250	X	X
1,1,1,2-TETRACHLOROETHANE	50.0	X	X
1,1,2,2-TETRACHLOROETHANE	50.0	X	X
TETRACHLOROETHENE	50.0	X	X
TOLUENE	50.0	BMQL	BMQL
1,1,1-TRICHLOROETHANE	50.0	X	67.3
1,1,2-TRICHLOROETHANE	50.0	X	X
TRICHLOROETHENE	50.0	X	X
TRICHLOROFLUOROMETHANE	50.0	X	X
VINYL CHLORIDE	50.0	X	X
XYLENES	50.0	X	X



WARZYN

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NORTH AMERICAN TOOL CORP.  
LOCATION: S. BELOIT, WISCONSIN  
C#: 15275.00

PAGE 3 OF 4  
CK'D:KDS APP'D:KDS  
DATE ISSUED: 10-23-92

COMPOUND	REPORTABLE DETECTION LIMIT (UG/KG AS REC'D)	1680-007(1) EXCAVATION- CONTAMINATED 9/10/90
=====	=====	=====
BENZENE	25.0	X
BROMOCHLOROMETHANE	50.0	X
BROMODICHLOROMETHANE	50.0	X
BROMOFORM	50.0	X
BROMOMETHANE	50.0	X
CARBON TETRACHLORIDE	50.0	X
CHLOROBENZENE	50.0	X
CHLORODIBROMOMETHANE	50.0	X
CHLOROETHANE	50.0	X
2-CHLOROETHYL VINYL ETHER	500	X
CHLOROFORM	50.0	X
CHLOROMETHANE	50.0	X
1,2-DIBROMO-3-CHLOROPROPANE	100	X
1,2-DICHLOROBENZENE	50.0	1450
1,3-DICHLOROBENZENE	50.0	X
1,4-DICHLOROBENZENE	50.0	X
1,1-DICHLOROETHANE	50.0	X
1,2-DICHLOROETHANE	50.0	BMQL
1,1-DICHLOROETHENE	50.0	X
CIS-1,2-DICHLOROETHENE	50.0	X
TRANS-1,2-DICHLOROETHENE	50.0	X
1,2-DICHLOROPROPANE	50.0	X
CIS-1,3-DICHLOROPROPENE	50.0	X
TRANS-1,3-DICHLOROPROPENE	50.0	X
ETHYL BENZENE	50.0	806
METHYLENE CHLORIDE	250	X
1,1,1,2-TETRACHLOROETHANE	50.0	X
1,1,2,2-TETRACHLOROETHANE	50.0	X
TETRACHLOROETHENE	50.0	1240
TOLUENE	50.0	X
1,1,1-TRICHLOROETHANE	50.0	1570
1,1,2-TRICHLOROETHANE	50.0	X
TRICHLOROETHENE	50.0	X
TRICHLOROFLUOROMETHANE	50.0	X
VINYL CHLORIDE	50.0	X
XYLENES	50.0	14600

WARZYN

MADISON  
ONE SCIENCE COURT  
P.O. BOX 5385  
MADISON, WI 53705  
(608) 231-4747  
FAX (608) 231-4777

VOLATILE ORGANIC COMPOUND RESULTS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NORTH AMERICAN TOOL CORP.  
LOCATION: S. BELOIT, WISCONSIN  
C#: 15275.00

PAGE 4 OF 4  
CK'D:KDJ APP'D:KDJ  
DATE ISSUED: 10-23-90

BMQL - DETECTED, VALUE BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

(1) SAMPLE CHROMATOGRAM CONTAINS UNIDENTIFIED COMPOUNDS.

METHOD REFERENCE: SW846, "TEST METHODS FOR EVALUATING  
SOLID WASTE", SEPTEMBER, 1986.  
METHODS 8010 AND 8020.

WARZYN

TOTAL PETROLEUM HYDROCARBONS  
WI LAB CERTIFICATION ID#: 113138300  
PROJECT: NORTH AMERICAN TOOL CORP.  
LOCATION: S. BELOIT, WISCONSIN  
C#: 15275.00

PAGE 1 OF 1  
CK'D:KDS APP'D:KDS  
DATE ISSUED: 10-23-90

METHOD  
REFERENCE: SW846, "TEST METHODS FOR EVALUATING  
SOLID WASTES", SEPTEMBER, 1986.  
METHOD 3550.

ASTM, "ANNUAL BOOK OF ASTM STANDARDS",  
1983. METHOD D-3328 WITH MODIFICATIONS.

NOTE: THE ANALYSIS OF SAMPLES FOR TOTAL PETROLEUM  
HYDROCARBONS IS A SCREENING PROCEDURE.  
ANALYTICAL RESULTS ARE COMPARED AND QUANTIFIED  
AGAINST KNOWN REFERENCE STANDARD MIXTURES. DUE TO  
VARIABLES SUCH AS DIFFERENCES IN PETROLEUM PRODUCT  
FORMULATIONS, WEATHERING AND OTHER ENVIRONMENTAL  
FACTORS, POSITIVE IDENTIFICATION AS ONE OF THE  
TARGET HYDROCARBON MIXTURES MAY NOT BE POSSIBLE.  
THE VALUES REPORTED ARE TENTATIVELY IDENTIFIED  
WITH ESTIMATED CONCENTRATIONS.

BMQL = DETECTED, BUT BELOW METHOD QUANTITATION LIMIT.  
X = ANALYZED, BUT NOT DETECTED.

- (1) SAMPLE 1680-007 CONTAINS WHAT APPEARS TO BE A  
HYDROCARBON FRACTION ELUTING OFF OF THE GAS CHROMATOGRAPH  
WITH A RETENTION TIME IN THE RANGE OF GASOLINE. THIS  
UNKNOWN DOES NOT MATCH ANY OF THE REFERENCE STANDARDS.  
AN ESTIMATED CONCENTRATION OF THE UNKNOWN CALCULATED  
AGAINST A GASOLINE REFERENCE STANDARD IS 2190 MG/KG.

COMPOUND =====	REPORTABLE DETECTION LIMIT (MG/KG AS REC'D) =====	1680-007 EXCAVATION- CONTAMINATED 9/10/90 =====
TOTAL HYDROCARBON AS:		
GASOLINE	5.00	X(1)
KEROSENE	5.00	X
#2 FUEL OIL	5.00	X

Madison, Wisconsin 53705  
 (608) 273-0440

Madison, Wisconsin 53705  
 (608) 273-0440